

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	02261118	Call Order: 002	Proposal: E21Z1	District:02
Counties:	TAYLOR			
Road Name:	SR51(RIVERSIDE DR) FROM 1ST AVE SOUTH TO RIVES AVE - RESURF			
Limits:	38070000			
Project(s):	40886725201(*)	Federal Aid No:	N/A	
Total Roadway Length:	1.597 Miles	Contract Days:	100	
Total Bridge Length:	0.000 Miles	Letting Date:	11/18/26	
Total Proposal Length:	1.597 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days (acq. time)	
Proposal Budget Estimate:	\$1,325,707.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, shoulder treatment, highway signing, guardrail, and other incidental construction on SR 51 (Riverside Dr) in Taylor County from 1st Ave South to Rives Ave. PREQUALIFICATION REQUIRED.

Call Order: 002 Proposal: E21Z1

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (40886725201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (40886725201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,300.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	18,200.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	364.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	228.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,670.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	22.000
	0107- 1-	LITTER REMOVAL	AC	26.440
	0107- 2-	MOWING	AC	23.070
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	223.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	1,233.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	23,736.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	2,077.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	6.500
	0527- 2-	DETECTABLE WARNINGS	SF	98.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	194.000
	0536- 8-111	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-2	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	174.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,086.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	367.900
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.104

Call Order: 002 Proposal: E21Z1

ALT	Item	Description	Unit	Quantity
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	57.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	390.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.091
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.570
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (40886725201)	LS	1.000
Section 0002 Signing				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	3.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	16.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	364.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (40886725201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	39.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	331.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.091
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	70.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.973
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.858
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	193.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.036
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.036