

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	02260916	Call Order: 002	Proposal: E21Z0	District:02
Counties:	CLAY, BRADFORD			
Road Name:	SR230 FROM BRADFORD COUNTY LINE TO SR16 - RESURFACING			
Limits:	71080000			
Project(s):	20820335201(*)	Federal Aid No:	N/A	
Project(s):	42448235201	Federal Aid No:	N/A	
Total Roadway Length:	7.353 Miles	Contract Days:	200	
Total Bridge Length:	0.057 Miles	Letting Date:	09/16/26	
Total Proposal Length:	7.410 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days (acq. time)	
Proposal Budget Estimate:	\$5,369,671.71			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, shoulder treatment, highway signing, guardrail, sidewalks/bicycle path, and other incidental construction on SR230 from Bradford County line to SR16 in Clay County and SR230 (E Call St) from Saint Clair St to Clay County Line in Bradford County. PREQUALIFICATION REQUIRED.

Call Order: 002 Proposal: E21Z0

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	732.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	22.300
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (20820335201)	LS	1.000
	0101- 1-	MOBILIZATION (42448235201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (20820335201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42448235201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (20820335201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (42448235201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	9,200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	42,400.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	18,158.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	2,888.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	600.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	400.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	291.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,003.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	8.000
	0107- 1-	LITTER REMOVAL	AC	949.800
	0107- 2-	MOWING	AC	850.570
	0110- 1- 1	CLEARING & GRUBBING (20820335201)	LS	1.000

Call Order: 002 Proposal: E21Z0

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (42448235201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	615.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	179.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	104,931.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	35,664.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	8,656.800
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	11,608.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	112.800
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0515- 2-111	PEDESTRIAN / BICYCLE RAILING, NS, 42" TYPE 1	LF	191.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	618.000
	0527- 2-	DETECTABLE WARNINGS	SF	340.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,712.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	14.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	8.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,351.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	8.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	29,050.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	3,860.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	29.596
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,076.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,264.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	954.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.456
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	12.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	16.296
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	566.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	7.164
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20820335201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42448235201)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	17.948
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	27.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	12.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	33.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,017.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (20820335201)	LS	1.000

Call Order: 002 Proposal: E21Z0

ALT	Item	Description	Unit	Quantity
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42448235201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	538.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,132.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	477.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.228
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	6.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	283.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	8.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	8.000
	0711- 14-180	THERMOPLASTIC, PREFORMED, WHITE, YIELD LINE	LF	12.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	14.798
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	8.148
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	3.582
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	1,232.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.171
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.057