

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03190411	Call Order: 004	Proposal: E3R27	District:03
Counties:	BAY			
Road Name:	BRIDGE-REPAIR/REHABILITATION			
Limits:	46020000			
Project(s):	40410835201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.152 Miles	Contract Days:	90	
Total Bridge Length:	0.076 Miles	Letting Date:	04/11/19	
Total Proposal Length:	0.228 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	45 Days	
Proposal Budget Estimate:	\$556,102.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of SR 30 (USB 98) 6th St Watson Bayou Bridge No. 460073 pile jacket installation, deck sealing, joint repair, fiber reinforced polymer security fencing installation, and other incidental work including Developmental work for Integrated multi-polymer markings located in Bay County, Florida (46020).

PREQUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 004 Proposal: E3R27

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 32-	CONCRETE FOR JOINT REPAIR	CY	5.700
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	10.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	6.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	50.000
	0413-151-	METHACRYLATE MONOMER	GA	252.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	25,200.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	60.000
	0457- 1- 22	STANDARD INTEGRAL PILE JACKET, STRUCTURAL, 16.1 to 30.0"	LF	6.000
	0457- 2-221	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	19.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	192.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (40410835201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (40410835201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,160.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,400.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	360.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	180.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	156.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	20.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	940.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	940.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	786.000
	0550- 10-803	FENCING, FIBER REINFORCED PLASTIC SECURITY FENCE, PROJECT 404108-3-52-01	LF	488.000
	0550- 60-803	FENCE GATE, FRP, SINGLE, 6.0', PROJECT 404108-3-52-01	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (40410835201)	LS	1.000
Section 0003 Signing				
	0706- 3-	RETRO-REFLECTIVE/RAISED PAVEMENT MARKERS	EA	78.000
	0918-712- 4	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SOLID 6", PROJECT 404108-3-52-01	GM	0.214
	0918-712- 5	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SKIP 6", PROJECT 404108-3-52-01	GM	0.182
	0918-712- 6	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, ARROW, PROJECT 404108-3-52-01	EA	2.000
	0918-712- 7	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, SOLID 6", PROJECT 404108-3-52-01	GM	0.284
	0918-712- 8	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, SOLID 18" FOR DIAGONAL OR CHEVRON, PROJECT 404108-3-52-01	LF	105.000