

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03190411 Call Order: 003 Proposal: E3S03 District:03

Counties: HOLMES

Road Name: SR 79 FROM CR 177 TO THE ALABAMA STATE LINE - RESURFACING

Limits: 52030000

Project(s): 43775215201(*) Federal Aid No: N/A

Total Roadway Length:	12.079 Miles	Contract Days:	240
Total Bridge Length:	0.089 Miles	Letting Date:	04/11/19
Total Proposal Length:	12.168 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Day

Proposal Budget Estimate: \$4,863,435.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of milling and resurfacing of SR 79 from CR 177 to the Alabama State line in Holmes County. Other work to be included are drainage and erosion Improvements, including the construction of concrete ditch pavement and riprap installation as well as replacement of existing cross drains and mitered end sections.

PREQUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 003 Proposal: E3S03

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	440.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	10.800
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43775215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43775215201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	155.100
	0102- 60-	WORK ZONE SIGN	ED	14,720.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	103,736.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	624.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	2,992.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	814.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	320.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	320.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,351.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	6.000
	0107- 1-	LITTER REMOVAL	AC	736.830
	0107- 2-	MOWING	AC	621.740
	0110- 1- 1	CLEARING & GRUBBING (43775215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	93.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	2.000
	0286- 1-	TURNOUT CONSTRUCTION	SY	86.000

Call Order: 003 Proposal: E3S03

ALT	Item	Description	Unit	Quantity
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	168,489.000
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	2,177.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	14,040.500
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	16,515.300
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	6.500
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	206.000
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD	LF	48.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	8.000
	0430-982-633	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 30" CD	EA	2.000
	0440- 1- 20	UNDERDRAIN, TYPE II	LF	326.000
	0440- 73- 2	UNDERDRAIN OUTLET PIPE, 6"	LF	8.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	125.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	1,728.000
	0527- 2-	DETECTABLE WARNINGS	SF	119.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	160.400
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	34,428.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	23.801
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	69.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	397.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	36.612
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	8.178
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43775215201)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	12.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	10.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	9.000
	0701- 18-101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	21.167
	0701- 18-201	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	12.871
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43775215201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	69.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	397.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.634
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.435
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	4.089