

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03190411 Call Order: 005 Proposal: E3S53 District:03

Counties: HOLMES

Road Name: PONCE DE LEON MAINTENANCE - SR 10 & SR 79 STRIPING

Limits:

Project(s): 42214327231

Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	30
Total Bridge Length:	0.000 Miles	Letting Date:	04/11/19
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$150,000.00

Please read the full advertisement

Description:

The Improvements under this Site-Specific Contract consist of the removal and replacement of existing reflective pavement markers and thermoplastic pavement markings along SR 79 and SR 10 (US 90) in Holmes County at locations shown in the Appendices. All work will be performed at night and a Traffic Control Officer will be required for all work zones. All items removed shall be replaced in same night. Mobilization and Maintenance of Traffic shall be incidental to the bid items listed.

Call Order: 005 Proposal: E3S53

ALT	Item	Description	Unit	Quantity
Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	240.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,904.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	723.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	50.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	350.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	11.053
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.896
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.550
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	3.355
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	53,000.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	1,130.000