

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03190808 Call Order: 002 Proposal: E3S85-R0 District:03
 Counties: DIST/ST-WIDE, HOLMES, WALTON, WASHINGTON
 Road Name: PONCE DE LEON MAINTENANCE - DRAINAGE REPAIRS
 Limits: Midpoint
 Project(s): 42214327254(*) Federal Aid No: N/A
 Total Roadway Length: 0.000 Miles Contract Days: Thru 06/30/20
 Total Bridge Length: 0.000 Miles Letting Date: 08/08/19
 Total Proposal Length: 0.000 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 days
 Proposal Budget Estimate: \$150,000.00

Please read the full advertisement

Description:

The Improvements under this Work Document-Driven Contract consist of repairing drainage failures on various State Roads throughout Holmes, Walton & a portion of Washington Counties. Work includes repair/replacement of drainage structures, replacement of damaged pipe, inlet caps, manhole covers, grates and frames. Other work may include replacement of mitered ends, desilting, sealing of pipes, pavement removal, sodding, sidewalk, curb and gutter and asphalt placement. Maintenance of Traffic and Mobilization are incidental to the bid items listed.

This contract has a budgetary ceiling of \$150,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

A Proposal Guaranty will not be required on indefinite quantity contracts, such as work document driven contracts, with an advertised budget amount of \$150,000 or less regardless of the bid amount.

Call Order: 002 Proposal: E3S85-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0104- 10- 3	SEDIMENT BARRIER	LF	100.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	50.000
	0110- 2- 1	CLEARING & GRUBBING (PUSH BUTTON CONTRACT)	AC	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	30.000
	0120- 1-	REGULAR EXCAVATION	CY	40.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	10.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	1.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	20.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	15.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	5.000
	0400- 2- 1	CONCRETE CLASS II, CULVERTS	CY	5.000
	0401- 70- 5	RESTORE SPALLED AREAS, CONTRACTORS OPTION	CF	5.000
	0425- 1-501	INLETS, DT BOT, TYPE A, <10'	EA	1.000
	0425- 1-502	INLETS, DT BOT, TYPE A, >10'	EA	1.000

Call Order: 002 Proposal: E3S85-R0

ALT	Item	Description	Unit	Quantity
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	5.000
	0425- 74- 1	MANHOLES & INLETS CLEANING & SEALING, <10'	EA	10.000
	0425- 74- 2	MANHOLES & INLETS CLEANING & SEALING, >10'	EA	5.000
	0425- 78-	INLET CAP, PRECAST	EA	1.000
	0425- 82-	REPLACE GRATE	EA	5.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	100.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	90.000
	0430- 94- 3	DESILTING PIPE, 37 - 48"	LF	80.000
	0430- 94- 4	DESILTING PIPE, 49 - 60"	LF	70.000
	0430- 94- 5	DESILTING PIPE, 61" OR GREATER	LF	60.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	50.000
	0430-173-124	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 24", GUTTER DRAIN	LF	50.000
	0430-173-136	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 36", GUTTER DRAIN	LF	50.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	50.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	50.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	50.000
	0430-174-136	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD	LF	40.000
	0430-174-148	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 48"SD	LF	30.000
	0430-821- 23	CLEANING & SEALING EXISTING PIPE JOINT, 15" STORM SEWER	EA	4.000
	0430-821- 25	CLEANING & SEALING EXISTING PIPE JOINT, 18" STORM SEWER	EA	10.000
	0430-821- 29	CLEANING & SEALING EXISTING PIPE JOINT, 24" STORM SEWER	EA	10.000
	0430-821- 33	CLEANING & SEALING EXISTING PIPE JOINT, 30" STORM SEWER	EA	5.000
	0430-821- 38	CLEANING & SEALING EXISTING PIPE JOINT, 36" STORM SEWER	EA	5.000
	0430-821- 40	CLEANING & SEALING EXISTING PIPE JOINT, 42", STORM SEWER	EA	5.000
	0430-821- 41	CLEANING & SEALING EXISTING PIPE JOINT, 48", STORM SEWER	EA	5.000
	0430-821- 42	CLEANING & SEALING EXISTING PIPE JOINT, 54", STORM SEWER	EA	1.000
	0430-821- 43	CLEANING & SEALING EXISTING PIPE JOINT, 60", STORM SEWER	EA	1.000
	0430-821- 61	CLEANING & SEALING EXISTING PIPE JOINT, >60", STORM SEWER	EA	1.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	5.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	5.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	5.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	5.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	2.000
	0430-984-141	MITERED END SECTION , OPTIONAL ROUND, 48" SD	EA	2.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0430-991- 1	MITERED END SECT, REPLACE SLAB- MAINTENANCE USE ONLY	CY	10.000
	0433- 1-	CHEMICAL GROUT REPAIR, MANHOLE / INLET	EA	5.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	30.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	30.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	30.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	10.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	10.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	5.000

Call Order: 002 Proposal: E3S85-R0

ALT	Item	Description	Unit	Quantity
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	150.000
	E110- 70-	REMOVAL OF FLEXIBLE PAVEMENT	SY	5.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	100.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	5.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	5.000
	E425- 73- 3	FRAME AND GRATE (F&I)	EA	5.000
	E425- 73- 4	RESET EXISTING FRAME AND GRATE	EA	5.000
	E425- 73- 5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	5.000
	E425- 73- 7	MANHOLE FRAME & COVER	EA	5.000
	E425- 73- 8	MANHOLE COVER	EA	5.000