Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting: 03190808 Call Order: 003 Proposal: E3S86 District:03

Counties: HOLMES, WALTON, WASHINGTON

Road Name: PONCE DE LEON MAINTENANCE - RIP-RAP RUBBLE BANK - SHORE

Limits: Midpoint

Project(s): 42214327257(*) Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: THRU 06/30/20

Total Bridge Length: 0.000 Miles Letting Date: 08/08/19

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 15 days

Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

Description:

Improvements under this Work Document-Driven Contract consist of the placement of Bank and Shore Riprap-Rubble as well as Ditch Lining Rubble along various roadways in Holmes, Walton and a portion of Washington Counties. This rubble will be used to fill, re-contour and restore eroded slope and ditch bottoms. Periodic lane closures will be required. Lane closures may be performed between 8:00 am and 3:00 pm with prior approval of the Engineer. Removal and replacement of guardrail may be necessary to accomplish dumping and spreading of rubble. All guardrail to be replaced at end of each work day. Mobilization, Maintenance of Traffic and removal & replacement of guardrail shall be incidental to the pay items listed.

This Contract has a budgetary ceiling of \$500,000.00.

Call Order: 003 Proposal: E3S86

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0104- 10- 3	SEDIMENT BARRIER	LF	300.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,000.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	400.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	15.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,600.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	900.000
	0530- 3- 9	RIPRAP- RUBBLE, REMOVE EXISTING AND REINSTALL - PUSH BUTTON ONLY	SF	10,000.000
	0530- 74-	BEDDING STONE	TN	1,600.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	500.000