

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03190711	Call Order: 001	Proposal: E3R72	District:03
Counties:	SANTA ROSA			
Road Name:	SR 4 RESURFACING			
Limits:	58080000			
Project(s):	43255415201(*)	Federal Aid No: N/A		
Project(s):	43255415202	Federal Aid No: N/A		
Project(s):	43255415601	Federal Aid No: N/A		
Total Roadway Length:	26.118 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	07/11/19	
Total Proposal Length:	26.118 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$5,278,916.00			

Please read the full advertisement

Description:

The Improvements under this District Contract for FPID 432554-1-52-01 consist of milling and resurfacing SR 4 from the Escambia River Bridge to CR 87A. Other improvements include curb and gutter and concrete sidewalk, drainage improvements, bridge joint replacement on Existing Bridges No. 580101, No. 580102, and No. 580095, guardrail construction, signalization and signing and pavement markings. FPID 432554-1-52-02 includes manhole and valve box adjustments. FPID 432554-1-56-01 includes constructing approximately 2,500 foot of water line in the Town of Jay along SR 4 from east of State Street to Magnolia Street, grouting/plugging unused water lines and roadway reconstruction. All work is to be done in Santa Rosa County.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 001 Proposal: E3R72

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43255415201)	LS	1.000
	0101- 1-	MOBILIZATION (43255415601)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43255415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43255415601)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	271.600
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	8.000
	0102- 60-	WORK ZONE SIGN	ED	12,060.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	49,376.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	4,186.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	4,338.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	388.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	180.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	180.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	360.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	360.000
	0104- 10- 3	SEDIMENT BARRIER	LF	426.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	18.000

Call Order: 001 Proposal: E3R72

ALT	Item	Description	Unit	Quantity
	0107- 1-	LITTER REMOVAL	AC	520.610
	0107- 2-	MOWING	AC	317.190
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43255415601)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43255415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,612.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	57.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	2,794.300
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43255415201)	LS	1.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	1,419.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	15.900
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	129,914.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	2,715.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	8,942.600
	0337- 7- 91	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, HIGH POLYMER	TN	13,983.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	30.900
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	21.000
	0425- 6-	VALVE BOXES, ADJUST	EA	12.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	3.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	973.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	224.600
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	598.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	407.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	340.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	1,042.000
	0527- 2-	DETECTABLE WARNINGS	SF	431.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	329.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	325.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	21,353.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	16.962
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	715.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	238.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	276.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	18.814
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	9.812
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43255415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43255415202)	LS	1.000

Call Order: 001 Proposal: E3R72

ALT	Item	Description	Unit	Quantity
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43255415601)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	26.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	10.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	11.000
	0700- 2- 11	MULTI- POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	4.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	12.008
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	4.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	14.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43255415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	715.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	238.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	276.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	218.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.088
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.406
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	4.906
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	9,397.000
	0918-712- 12	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SOLID 6", PROJECT 432554-1-52-01	GM	2.586
	0918-712- 13	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, SOLID 6", PROJECT 432554-1-52-01	GM	0.769
	0918-712- 14	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, 10-30 SKIP 6", PROJECT 432554-1-52-01	GM	1.054
Section 0003 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	393.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	2.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	3.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	3.000

Call Order: 001 Proposal: E3R72

ALT	Item	Description	Unit	Quantity
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	2.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	2.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	2.000
Section 0004 Utilities				
	1050- 31-202	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 2"	LF	21.000
	1050- 31-206	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	157.000
	1050- 31-208	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 8"	LF	2,289.000
	1050- 42-208	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 8"	LF	60.000
	1050- 42-210	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 10"	LF	240.000
	1055- 31-108	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, ELBOW, 8"	EA	28.000
	1055- 31-208	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, TEE, 8"	EA	12.000
	1055- 31-508	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, CAP/PLUG, 8"	EA	7.000
	1080- 23-100	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 1"	EA	16.000
	1080- 23-102	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 2"	EA	2.000
	1080- 23-106	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 6"	EA	4.000
	1080- 23-108	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 8"	EA	3.000
	1080- 24-106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	10.000
	1080- 24-108	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 8"	EA	11.000