

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03190711 Call Order: 003 Proposal: E3S82 District:03

Counties: JACKSON, WASHINGTON

Road Name: JACKSON & WASHINGTON COUNTY - HURRICANE MICHAEL - EMERGENCY

Limits: Midpoint

Project(s): 4454801G201(*) Federal Aid No: N/A

Project(s): 4454811G201 Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	07/11/19
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$2,000,000.00

Please read the full advertisement

Description:

The Improvements under this Work Document-driven Contract consist of the refurbishment of roadway shoulders and reshaping of ditches and establishment of turf for stabilization purposes, along shoulders, front slopes and back slopes of designated areas along SR 8 (Interstate 10) and SR 10 (US 90) as determined by the Engineer and directed on each work document. The rework areas have suffered damage from Hurricane Michael clean-up efforts and may require additional fill material and remaining hurricane debris removal and disposal which is incidental to the pay items listed. Maintenance of Traffic and Mobilization will be incidental to the pay items listed.

This contract has a budgetary ceiling of 2,000,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Call Order: 003 Proposal: E3S82

ALT	Item	Description	Unit	Quantity
Section 0001 SODDING (SY)				
	0120- 10- 11	CLEAN AND RESHAPE DITCH, SPREAD, DITCH WIDTH UP TO 15'	LF	2,000.000
	0120- 10- 12	CLEAN AND RESHAPE DITCH, SPREAD, DITCH WIDTH 15-30'	LF	2,000.000
	0120- 10- 13	CLEAN AND RESHAPE DITCH, SPREAD, DITCH WIDTH GREATER THAN 30'	LF	1,000.000
	0120- 10- 21	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH UP TO 15'	LF	1,000.000
	0120- 10- 22	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH 15-30'	LF	1,000.000
	0120- 10- 23	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH GREATER THAN 30'	LF	551.000
	0570- 1- 1	PERFORMANCE TURF	SY	75,000.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,000.000
	E577- 70-	SHOULDER REWORK	SY	730,000.000
	E577- 71-	BLADING PAVED SHOULDER, UP TO 24" BEYOND PAVEMENT	LF	120,000.000