

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	03190509	Call Order: 001	Proposal: E3Q54	District:03
Counties:	GADSDEN			
Road Name:	I-10 (SR 8)			
Limits:	50001027			
Project(s):	22253925201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.253 Miles	Contract Days:	90	
Total Bridge Length:	0.059 Miles	Letting Date:	05/09/19	
Total Proposal Length:	0.312 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$1,155,497.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of bridge painting and other incidental construction for I-10 Rest Area Ramp over SR 8 (I-10), Bridge Nos. 500075 and 500076, in Gadsden County.

PREQUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 001 Proposal: E3Q54**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0460- 81-	RIVETS - HIGH STRENGTH BOLTS, REPLACEMENT	EA	600.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (22253925201)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (22253925201)	LS	1.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (22253925201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (22253925201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (22253925201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,050.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,190.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	90.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	90.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	180.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	180.000
	0107- 1-	LITTER REMOVAL	AC	18.760
	0107- 2-	MOWING	AC	18.760
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	1,411.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	1,693.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	77.600
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	67.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	41.400
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	813.000
	0536- 73-	GUARDRAIL REMOVAL	LF	794.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	1.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.200
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	375.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.241
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (22253925201)	LS	1.000