

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	03190509	Call Order: 003	Proposal: E3R84	District:03
Counties:	HOLMES			
Road Name:	SR 79			
Limits:	52030000			
Project(s):	21915525201	Federal Aid No:	N/A	
Project(s):	43736715201(*)	Federal Aid No:	N/A	
Project(s):	43736715601	Federal Aid No:	N/A	
Total Roadway Length:	6.683 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	05/09/19	
Total Proposal Length:	6.683 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	50 Days	
Proposal Budget Estimate:	\$1,969,287.00			

Please read the full advertisement

**Description:**

The Improvements under this District Contract consist of FPID 437367-1-52-01 (SR 79 Waukesha Street from North of SR 8 (I-10) to SR 10 (US 90) which includes milling and resurfacing, minor widening, signing and pavement markings, minor signal upgrades (loops) and base work. FPID 437367-1-56-01 includes "Utility Work by Highway Contractor". Construction of new watermain from Brock Avenue to North of SR 10 (US 90). FPID 219155-2-52-01, includes box culvert replacement south of R/R crossing g/w 437367-1-52-01 R/W to include TCE agreements only offsite. All work is in Holmes County. The summary of pay items for this project is listed in the Plans.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

**Call Order: 003 Proposal: E3R84**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (21915525201)	LS	1.000
	0101- 1-	MOBILIZATION (43736715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21915525201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43736715201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	20.000
	0102- 60-	WORK ZONE SIGN	ED	31,655.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	88,924.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	202.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	138.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	240.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	2,541.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	918.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	150.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	150.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,563.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	20.000
	0107- 1-	LITTER REMOVAL	AC	50.200

**Call Order: 003 Proposal: E3R84**

ALT	Item	Description	Unit	Quantity
	0107- 2-	MOWING	AC	41.830
	0110- 1- 1	CLEARING & GRUBBING (21915525201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43736715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	320.000
	0120- 1-	REGULAR EXCAVATION	CY	50.000
	0120- 6-	EMBANKMENT	CY	280.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	183.000
	0160- 4-	TYPE B STABILIZATION	SY	657.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	1,935.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	121.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	632.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	536.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	42,232.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	12,057.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	145.000
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	26.900
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	4,573.000
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	149.200
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	19,844.000
	0425- 1-321	INLETS, CURB, TYPE P-2, <10'	EA	1.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	1.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	2.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	60.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	13.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	0.900
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY, 42" TYPE 1	LF	48.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	148.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	119.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	201.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	2.900
	0530- 5- 2	GABION, 1 FOOT AND GREATER THICKNESS	SY	17.000
	0530- 74-	BEDDING STONE	TN	2.100
	0570- 1- 1	PERFORMANCE TURF	SY	1,805.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,315.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	1.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.380
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.080
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	172.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	35.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	356.000

**Call Order: 003 Proposal: E3R84**

ALT	Item	Description	Unit	Quantity
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.311
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.069
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	70.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.280
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	207.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	2.190
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21915525201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43736715201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	2.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	12.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21915525201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43736715201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.080
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	172.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	35.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	356.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.069
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	70.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	207.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	348.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	6.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	6.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.418
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.311
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.318
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.240
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	2.190
<b>Section 0003 Utilities</b>				
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	726.600
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	68.000

**Call Order: 003 Proposal: E3R84**

ALT	Item	Description	Unit	Quantity
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	632.000
	0160- 4-	TYPE B STABILIZATION	SY	1,525.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	661.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	50.300
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	57.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	68.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43736715601)	LS	1.000
	1050- 31-202	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 2"	LF	67.000
	1050- 31-206	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	1,878.000
	1050- 42-206	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	1,050.000
	1080- 24-106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	12.000
	1080- 29-106	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 6"	EA	20.000