

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	03190912	Call Order: 001	Proposal: E3R70	District:03
Counties:	LEON			
Road Name:	SR 263			
Limits:	55002000			
Project(s):	43814115201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.218 Miles	Contract Days:	60	
Total Bridge Length:	0.000 Miles	Letting Date:	09/12/19	
Total Proposal Length:	0.218 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Day Standard Acq.	
Proposal Budget Estimate:	\$496,712.00			

Please read the full advertisement

**Description:**

The Improvements under this District Contract are for the SR 263 (US 319) Capital Circle at Stoneler Road Intersection. The Items of Work consist of widening, milling and resurfacing, base work, drainage improvements, curb and gutter, highway signing and other incidental construction in Leon County.

**BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <http://www.fdot.gov/equalopportunityoffice/bdi.shtm>. For more information about bidding on BDI projects, please see the training guide located at <http://www.cmdp-bgp.com/bdi-projects.html> Prequalification per Rule 14-22 is not required. Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <http://www.fdot.gov/contracts/forms/forms.shtm> It is only necessary to submit the Small Business Affidavit (SBA) form once per year. Send a completed and notarized affidavit as an attachment to: [fdot.bdi@dot.state.fl.us](mailto:fdot.bdi@dot.state.fl.us). All Sublet work must be contracted to a small business or businesses as defined by the Department. The subcontractor must also submit a notarized Small Business Affidavit Form provided by the Department prior to the start of work. Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the projects major work type, per Rule 14-22, Florida Administrative Code. Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the Expedite application. BDI Reference Sheet may be found at: <http://www.fdot.gov/equalopportunityoffice/bdi.shtm> Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashiers Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09). A Contract Bond is not required for contracts \$250,000.00 and less.**

**Call Order: 001 Proposal: E3R70**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43814115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43814115201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,077.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,679.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	148.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,635.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	118.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	6.000
	0107- 1-	LITTER REMOVAL	AC	2.250
	0107- 2-	MOWING	AC	1.930
	0110- 1- 1	CLEARING & GRUBBING (43814115201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	577.700

**Call Order: 001 Proposal: E3R70**

ALT	Item	Description	Unit	Quantity
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,437.000
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	747.000
	0285-732-	OPTIONAL BASE- GRADED AGGREGATE, 16" FOR PROJECT 438141-1-52-01	SY	682.000
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	1,854.000
	0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY	940.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	623.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	165.100
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	327.200
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	4.500
	0425- 1-421	INLETS, CURB, TYPE J-2, <10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	1.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	1.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	134.000
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD	LF	304.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	1.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	154.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	35.700
	0530- 74-	BEDDING STONE	TN	21.200
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	46.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	2,978.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.398
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	37.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.011
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	8.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.644
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	101.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43814115201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	3.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43814115201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	37.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.011
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	5.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	101.000

**Call Order: 001 Proposal: E3R70**

ALT	Item	Description	Unit	Quantity
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	3.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	3.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.398
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.644