

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 03190912      Call Order: 004      Proposal: E3S96      District:03  
Counties: JACKSON, WASHINGTON  
Road Name: JACKSON & WASHINGTON COUNTY - HURRICANE MICHAEL - EO  
Limits: Midpoint  
Project(s): 4454801G201(\*)      Federal Aid No: N/A  
Project(s): 4454811G201      Federal Aid No: N/A  
Total Roadway Length: 0.000 Miles      Contract Days: 365  
Total Bridge Length: 0.000 Miles      Letting Date: 09/12/19  
Total Proposal Length: 0.000 Miles      Contract Execution Days: 10  
Special Start Date: N/A  
Aquis/Flexible Start Time: 15 DAYS

Proposal Budget Estimate: \$2,793,000.00

Please read the full advertisement

Description:

The Improvements under this Site-Specific Contract consist of the refurbishment of roadway shoulders and reshaping of ditches and establishment of turf for stabilization purposes, along shoulders, front slopes and back slopes of designated areas along SR 8 (Interstate 10) and SR 10 (US 90) in Jackson and Washington Counties. The rework areas have suffered damage from Hurricane Michael cleanup efforts and may require additional fill material and remaining hurricane debris removal and disposal which is incidental to the pay items listed. Maintenance of Traffic and Mobilization will be incidental to the pay items listed.

7-13.2 Commercial General Liability Insurance: The limits of coverage shall not be less than \$1,000,000 for any one person, not less than \$5,000,000 for each occurrence, and not less than a \$5,000,000 annual general aggregate, inclusive of amounts provided by an umbrella or excess policy.

**Call Order: 004 Proposal: E3S96**

---

ALT	Item	Description	Unit	Quantity
<b>Section 0001 TRAFFIC CONTROL DEVICES CONTROL (MH)</b>				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	100.000
	0120- 10- 11	CLEAN AND RESHAPE DITCH, SPREAD, DITCH WIDTH UP TO 15'	LF	1,000.000
	0120- 10- 21	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH UP TO 15'	LF	38,218.000
	E570- 2-	SEED & MULCH	SY	1,088,494.000
	E577- 70-	SHOULDER REWORK	SY	1,088,494.000
	E577- 71-	BLADING PAVED SHOULDER, UP TO 24" BEYOND PAVEMENT	LF	1,400.000