## Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting: 03190912 Call Order: 007 Proposal: E3T02 District:03

Counties: HOLMES

Road Name: PONCE DE LEON MAINTENANCE - SR 2

Limits: Midpoint

Project(s): 42214327260(\*) Federal Aid No: N/A

Total Roadway Length:0.000 MilesContract Days:120Total Bridge Length:0.000 MilesLetting Date:09/12/19Total Proposal Length:0.000 MilesContract Execution Days:10

Special Start Date: N/A

Aquis/Flexible Start Time: 15 DAYS

Proposal Budget Estimate: \$318,000.00

Please read the full advertisement

## Description:

The Improvements under this Site-Specific Contract consist of reshaping ditches and reworking shoulders along State Road 2 in Holmes County at designated locations, from Holmes County Road 177 (Mile Post 20.835) to Holmes County Road 173 (Mile Post 31.056). These ditches are non-typical and should be re-graded to +/- 3 inches of the original flow line to create a free and unobstructed flow of drainage water. For the purposes of this contract, the original flow line is considered to be the linear projection along the ditch bottom between the invert elevations of immediately adjacent drainage structures. Spoil material removed from ditches and shoulders shall be relocated to FDOT storage pit in Argyle or at 0.10 miles east of Wrights Creek Road (Mile Post 29.707) on SR 2. Mobilization and Maintenance of Traffic shall be incidental to the bid items.

Call Order: 007 Proposal: E3T02

•				
ALT	Item	Description	Unit	Quantity
Section 0001 SODDING (SY)				
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	20.000
	0104- 10- 3	SEDIMENT BARRIER	LF	300.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	50,630.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	12,500.000
	E577- 70-	SHOULDER REWORK	SY	50,630.000