



Vendor Ranking

Letting: 03210114 January 14, 2021 2:00 PM **Call Order:** 003 **Contract:** E3U48
District: District 3 **Counties:** SANTA ROSA **Fed Aid No:** N/A
Contract Time: 60 CALENDAR DAYS **Project(s):** 42214237201 (*)
Contract Desc: MILTON MAINTENANCE - SR10 DITCH/DRAINAGE WORK

Rank	Vendor	Bid Type	Bid Status	Total Bid	Percent Of Low Bid
1	ROADS, INC. OF NWF	Responsive	Winning bid	\$319,420.00	100.00%
2	PANHANDLE GRADING & PAVING, INC.	Responsive	Non-Winning Bid	\$450,185.99	140.94%
3	ROGAR MANAGEMENT & CONSULTING OF FLORIDA LLC	Responsive	Non-Winning Bid	\$533,611.60	167.06%

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

NOTICE OF INTENT TO AWARD: AWARD AND EXECUTION CONTINGENT UPON BUDGET AVAILABILITY



Tabulation of Bids

Letting: 03210114 January 14, 2021 **Call Order:** 003 **Contract:** E3U48
District: District 3 **Counties:** SANTA ROSA **Fed Aid No:** N/A
Contract Time: 60 CALENDAR DAYS **Project(s):** 42214237201 (*)

Contract Descr: MILTON MAINTENANCE - SR10 DITCH/DRAINAGE WORK

Improvements under this Site-Specific Lump Sum contract consist of upgrading the drainage system in the northeast quadrant of the intersection of SR 10 (US 90) and Glover Lane in Santa Rosa County (MP 10.352). Remove the existing mitered end section and install a junction box with a Type J-8 traffic-bearing manhole on a 12 inch thick bedding stone base. Use flowable fill in lieu of embankment around the junction box to an elevation above the pipe connections. Extend the existing 36 inch reinforced concrete pipe (RCP) side drain at Glover Lane to connect to the junction box. From the junction box, install approximately 20 LF of 24-inch RCP and mitered end section to tie into the existing ditch Northeast of SR 10 and install 30 LF of 36 inch RCP and mitered end section to tie into the existing ditch East of Glover Lane. Increase the existing radius at Glover Lane to encompass the new junction box and manhole using concrete pavement with a minimum thickness of 6-inches. Newly installed pipe locations shall be backfilled, and sod installed to match existing shoulder elevations to prevent erosion. Install riprap rubble ditch lining for approximately 300 LF eastward from Glover Lane along the ditch bottom (approximately 6), front slope (approximately 4), and back slope (approximately 4). All existing flowlines shall be maintained. Restore any damaged asphalt pavement and shoulders to pre-existing conditions. All work shall be completed within the existing FDOT right of way. All work requiring a lane closure will be performed at night. Mobilization and Maintenance of Traffic shall be incidental to the pay items listed.

Line No / Item ID Item Description () indicates item is bid as Lump Sum	Alternate	Quantity Units	(1) ROADS, INC. OF NWF		(2) PANHANDLE GRADING & PAVING, INC.		(3) ROGAR MANAGEMENT & CONSULTING OF FLORIDA LLC	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 (CONCRETE REPAIR (CY								
0005 E999 10 41 MAINTENANCE LUMP SUM CONTRACT		(1.000) LS	319,420.00000	319,420.00	450,185.99000	450,185.99	533,611.60000	533,611.60
0001 CONCRETE REPAIR (CY) Section Totals:				\$319,420.00		\$450,185.99		\$533,611.60
Contract Grand Totals:				\$319,420.00		\$450,185.99		533,611.60



Tabulation of Bids

Letting: 03210114 January 14, 2021 **Call Order:** 003 **Contract:** E3U48

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.