

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	03191212	Call Order: 004	Proposal: E3S73	District:03
Counties:	FRANKLIN, GULF			
Road Name:	HURRICANE MICHAEL - EMERGENCY OPERATIONS			
Limits:	49010001			
Project(s):	4453811H201(*)	Federal Aid No:	E191123E	
Project(s):	4453821H201	Federal Aid No:	E191125E	
Project(s):	4453831H201	Federal Aid No:	E191124E	
Project(s):	4453841H201	Federal Aid No:	E191122E	
Project(s):	4453851H201	Federal Aid No:	E191126E	
Total Roadway Length:	6.743 Miles	Contract Days:	150	
Total Bridge Length:	6.743 Miles	Letting Date:	12/12/19	
Total Proposal Length:	13.486 Miles	Contract Execution Days:	5	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	45 Days Acquis. Time	
Proposal Budget Estimate:	\$182,772.00			

Please read the full advertisement

Description:

This Permanent Repair Contract shall consist of the repair/replacement of navigation lights systems, fender systems, clearance gauges, bridge deck lighting, and underdeck lighting at each identified bridge location. All lighting repairs shall be fully functional and operational upon completion to ensure lights are illuminating at the appropriate times. Any associated service connection fees shall be included in the cost of the repair pay item. Navigational light repairs shall include replacement of the existing center channel lights, demolition of existing wiring/conduit and navigation fixtures from bridge fender systems and furnishing and installing new navigation fixtures, center channel lights, and clearance gauge lights. This will include but not be limited to conduit, conductors, disconnect switches, and J boxes on bridge fender systems and down pier columns. Repair/Replacement items shall be in-kind and match pre-event locations. Navigation lights shall be LED light source.

FHWA 1273 AND DAVIS BACON WAGE RATES ARE APPLICABLE FOR THIS CONTRACT

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 004 Proposal: E3S73**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0101- 1-	MOBILIZATION (4453811H201)	LS	1.000
	0101- 1-	MOBILIZATION (4453821H201)	LS	1.000
	0101- 1-	MOBILIZATION (4453831H201)	LS	1.000
	0101- 1-	MOBILIZATION (4453841H201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (4453811H201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (4453851H201)	LS	1.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	3.000
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (4453811H201)	LS	1.000
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (4453821H201)	LS	1.000
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (4453831H201)	LS	1.000
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (4453841H201)	LS	1.000
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (4453851H201)	LS	1.000
	0510- 1- 4	NAVIGATION LIGHTS- FIXED BRIDGE, REPAIR/REHAB	EA	1.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	1.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	1.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	4.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	4.000
	0715- 11-600	LUMINAIRE, REPAIR & REINSTALL	EA	20.000
	0715- 21- 6	LUMINAIRE, NAVIGATION LIGHTS, REMOVE	EA	40.000