

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03191114 Call Order: 002 Proposal: E3R78 District:03

Counties: BAY

Road Name: SR 75 (US 231) at 19th St. Intersection

Limits: 46040000

Project(s): 43813815201(*) Federal Aid No: N/A

Total Roadway Length:	0.122 Miles	Contract Days:	90
Total Bridge Length:	0.000 Miles	Letting Date:	11/14/19
Total Proposal Length:	0.122 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60 Days

Proposal Budget Estimate: \$524,707.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of constructing a southbound right turn lane on SR 75 (US 231) at 19th St intersection in Bay County. Other construction activities include signing and pavement markings as well as modifications to a signalized intersection.

PRE-QUALIFICATION REQUIRED TO BID ON THIS PROJECT

Call Order: 002 Proposal: E3R78

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43813815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43813815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,235.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,589.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	396.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	194.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	90.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	90.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,799.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	7.000
	0107- 1-	LITTER REMOVAL	AC	6.830
	0107- 2-	MOWING	AC	3.250
	0110- 1- 1	CLEARING & GRUBBING (43813815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4.000
	0120- 1-	REGULAR EXCAVATION	CY	236.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	121.000
	0160- 4-	TYPE B STABILIZATION	SY	1,278.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	692.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	542.000
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	11,964.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	108.400

Call Order: 002 Proposal: E3R78

ALT	Item	Description	Unit	Quantity
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	901.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	8.600
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	125.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,187.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.758
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.708
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.813
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.140
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43813815201)	LS	1.000
Section 0002 Signing				
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	3.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43813815201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	125.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	220.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	64.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.018
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	22.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	232.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.011
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	125.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	119.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.787
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.554
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.732
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.408
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	125.000
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	134.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0650- 1- 70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	4.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	10.000

Call Order: 002 Proposal: E3R78

ALT	Item	Description	Unit	Quantity
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	1.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	1.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000
	0682- 1-132	ITS CCTV CAMERA, F&I, DOME PTZ - NON-PRESSURIZED, IP, STANDARD DEFINITION	EA	1.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	1.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000