

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03191114 Call Order: 003 Proposal: E3S48 District:03

Counties: WAKULLA

Road Name: SR 377/375 (US 319)

Limits: 59030000

Project(s): 43973015201(*) Federal Aid No: N/A

Total Roadway Length:	8.889 Miles	Contract Days:	150
Total Bridge Length:	0.000 Miles	Letting Date:	11/14/19
Total Proposal Length:	8.889 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$2,776,728.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of milling and resurfacing, minor widening, turnout construction, drainage and guardrail improvements, signing and pavement markings along SR 377/375 (US 319) Sopchoppy Highway from North of Beasley Road to SR 30 (US 98) in Wakulla County, Florida.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 003 Proposal: E3S48

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43973015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43973015201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	299.800
	0102- 60-	WORK ZONE SIGN	ED	17,100.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	15,516.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	471.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,140.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	194.620
	0107- 2-	MOWING	AC	146.410
	0110- 1- 1	CLEARING & GRUBBING (43973015201)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	66.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43973015201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	470.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	380.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	39.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	235.800
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	156,823.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	3.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	13,059.600
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	71.500

Call Order: 003 Proposal: E3S48

ALT	Item	Description	Unit	Quantity
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	4.300
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	1.000
	0425- 82-	REPLACE GRATE	EA	1.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	68.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	447.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	600.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	8.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	40.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	24.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	18.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	16.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	2.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	32.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	30.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	2.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0431- 1-231	PIPE LINING- CURED IN PLACE, 30" PROJECT 439730-1-52-01	LF	96.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	47.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,675.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	2.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,597.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	6.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	22,771.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43973015201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	46.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	4.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	38.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	4.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	3.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	4.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	16.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	5.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	10.967
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	2.780
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43973015201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.031

Call Order: 003 Proposal: E3S48

ALT	Item	Description	Unit	Quantity
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	180.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	153.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.049
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	6.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	213.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.263
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.888
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	4.714
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.052
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.052