

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03191114 Call Order: 011 Proposal: E3T31 District:03

Counties: JACKSON

Road Name: JACKSON COUNTY HURRICANE MICHAEL - EMERGENCY OPERATIONS

Limits: Midpoint

Project(s): 4454801D201(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	11/14/19
Total Proposal Length:	0.000 Miles	Contract Execution Days:	15
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$1,000,000.00

Please read the full advertisement

Description:

The Improvements under this Site-Specific Contract consist of restoring outfall ditches for the state road system within Jackson County. The purpose of this work is to cut and remove fallen trees, stumps, vegetation, debris, remove construction and demolition debris located within the outfall ditch areas, clean and maintain the outfall ditches to address drainage issues caused by Hurricane Michael. Access to ditches may be limited. Contractor should have a plan to clear ditch from within the limits of the ditch. If right of entry is required, contractor shall restore property to original condition at no cost to the department. Due to the destructive forces of the hurricane, re-shaping of ditches may be required. The removal and disposal of the debris generated in the performance of the contract is incidental to the pay items listed. Maintenance of Traffic, Mobilization, and Erosion control devices will be incidental to the pay items listed.

Call Order: 011 Proposal: E3T31

ALT	Item	Description	Unit	Quantity
Section 0001 SODDING (SY)				
	0120- 9- 1	DITCH CLEARING OF LARGE VEGETATION, DITCH WIDTH UP TO 15'	LF	300.000
	0120- 9- 2	DITCH CLEARING OF LARGE VEGETATION, DITCH WIDTH 15-30'	LF	10,538.000
	0120- 9- 3	DITCH CLEARING OF LARGE VEGETATION, DITCH WIDTH GREATER THAN 30'	LF	18,042.000
	0120- 10- 11	CLEAN AND RESHAPE DITCH, SPREAD, DITCH WIDTH UP TO 15'	LF	300.000
	0120- 10- 12	CLEAN AND RESHAPE DITCH, SPREAD, DITCH WIDTH 15-30'	LF	5,546.000
	0120- 10- 13	CLEAN AND RESHAPE DITCH, SPREAD, DITCH WIDTH GREATER THAN 30'	LF	9,496.000
	0120- 10- 21	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH UP TO 15'	LF	300.000
	0120- 10- 22	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH 15-30'	LF	6,656.000
	0120- 10- 23	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH GREATER THAN 30'	LF	11,395.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	300.000
	0530- 74-	BEDDING STONE	TN	300.000
	0570- 1- 1	PERFORMANCE TURF	SY	30,083.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	25,070.000
	E570- 2-	SEED & MULCH	SY	7,304.000