

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03191010 Call Order: 003 Proposal: E3T08 District:03

Counties: WALTON

Road Name: PONCE DE LEON MAINTENANCE - DITCH RESHAPE

Limits: Midpoint

Project(s): 42214327265(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	120
Total Bridge Length:	0.000 Miles	Letting Date:	10/10/19
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 DAYS

Proposal Budget Estimate: \$569,180.00

Please read the full advertisement

Description:

The Improvements under this Site-Specific Contract consist of reshaping ditches and reworking shoulders along State Road 83 in Walton County at designated locations, from Morris Drive (Mile Post 0.533) to Alabama State Line (Mile Post 19.116). These ditches are non-typical and should be re-graded to +/- 3 inches of the original flow line to create a free and unobstructed flow of drainage water. For the purposes of this contract, the original flow line is considered to be the linear projection along the ditch bottom between the invert elevations of immediately adjacent drainage structures. Spoil material removed from ditches and shoulders shall be relocated to FDOT storage pit in Argyle. Mobilization and Maintenance of Traffic shall be incidental to the bid items.

Call Order: 003 Proposal: E3T08

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MANUAL) (TN)				
	0104- 10- 3	SEDIMENT BARRIER	LF	500.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	60.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	29,000.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	29,320.000
	E577- 70-	SHOULDER REWORK	SY	209,700.000