

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	03191014	Call Order: 002	Proposal: E3T19	District:03
Counties:	JACKSON			
Road Name:	SR 8 (I-10) AT EASTBOUND JACKSON COUNTY REST AREA			
Limits:	53002000			
Project(s):	4453861K201(*)	Federal Aid No:	E191130E	
Project(s):	4453862K201	Federal Aid No:	E191130E	
Total Roadway Length:	0.482 Miles	Contract Days:	70	
Total Bridge Length:	0.000 Miles	Letting Date:	10/14/19	
Total Proposal Length:	0.482 Miles	Contract Execution Days:	5	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	45 Days Acquis.	
Proposal Budget Estimate:	\$276,141.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of Permanent repair/replacement of damaged items at the SR 8 (I-10) Rest Areas in Jackson County. Location of Repair Items can be found in the attached Jackson County Rest Area Repair Items Google Earth KMZ file. Each location provided in the KMZ file is approximate and subject to variability of quantified damage and location accuracy. All information provided within the KMZ file is provided for information only. Suggested sign messages provided within the KMZ file shall be coordinated with and approved by the Engineer prior to ordering of new signs. To navigate to each location of damage within the KMZ file, under the "Places" tab, ensure that all subfolders are open, and double-click on the desired item. Bids shall be based on the quantities reflected within the Bid Sheet. Additional damaged items noted in the field shall be repaired at the direction of the Engineer and will be compensated through a supplemental agreement. Except to the extent inconsistent with provisions in this document, which supersedes all other governing documents, all work shall be in accordance with the July 2019 Standard Specifications for Road and Bridge Construction, the FY 2019-20 Standard Plans for Road and Bridge Construction, and the 2017 Florida Building Code.

FHWA 1273 AND DAVIS BACON WAGE RATES ARE APPLICABLE FOR THIS CONTRACT

If YOU WILL BE SUBMITTING A BID AND WOULD LIKE TO EXAMIN THE SITE OF WORK SITES WILL BE AVAILABLE FOR EXAMIINATION ON THE FOLLOWING DATE AND TIME:
THE WEST BOUND REST AREA SITE VISIT IS SCHEDULED FOR SEPTEMBER 23, 2019 @ 1:00 PM CST TIME. THE EAST BOUND REST AREA SITE VISIT WILL BEGIN IMMIDIEATLY AFTER.

Prequalification per rule 14-22 is not required. A Builder's License or General Contractor's License is required for this project. For buildings three (3) stories or less in height, a Builder's License or General Contractor's License is acceptable. Buildings more than 3 stories in height require a General Contractor's License. This building is less than 3 stories in height.

A COPY OF THE LICENSE MUST BE RECEIVED PRIOR TO AWARD.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 002 Proposal: E3T19

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (4453861K201)	LS	1.000
	0101- 1-	MOBILIZATION (4453862K201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (4453861K201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (4453862K201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,500.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	130.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	10.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	250.000
	0550- 10-221	FENCING, TYPE B, 5.1-6.0', W/ BARB WIRE ATTMT	LF	250.000
	0550- 10-222	FENCING, TYPE B, 5.1-6.0, W/ VINYL COATING	LF	20.000
	0550- 60-211	FENCE GATE, TYPE B, SINGLE, 0- 6.0' OPENING	EA	1.000
	0550- 60-233	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 12.1-18' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	100.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	7.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	15.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	8.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	8.000
	0715- 11-118	LUMINAIRE, F&I, ROADWAY, FLOOD	EA	2.000
	0715-516-115	LIGHT POLE COMPLETE-SPECIAL DESIGN, F&I, POLE TOP MOUNT, ALUMINUM, 15'	EA	2.000
	0715-518-115	LIGHT POLE COMP- SPECIAL DESIGN, F&I, DOUBLE ARM, POLE TOP MOUNT, ALUMINUM, 15'	EA	2.000
	0715-550-000	LIGHT POLE COMPLETE- SPECIAL DESIGN, REMOVE	EA	4.000
Section 0002 Architectural				
	0751- 6-	ARCHITECTURAL- HVAC (4453861K201)	LS	1.000
	0751- 7-	ARCHITECTURAL- ROOF REPAIRS (4453861K201)	LS	1.000