

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03200409 Call Order: 010 Proposal: E3T80 District:03

Counties: LEON

Road Name: MIDWAY MAINTENANCE - OVERHEAD SIGN PANELS

Limits: Midpoint

Project(s): 42215127230(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	120
Total Bridge Length:	0.000 Miles	Letting Date:	04/09/20
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$600,000.00

Please read the full advertisement

Description:

The work under this Site-Specific Contract includes the removal and replacement of identified Overhead Lighted Guide Sign Panels to include supplemental panels in Leon County as listed in the Appendices, as well as supplying all associated attachment hardware and incidentals (new components). Other work associated with this contract consists of the removal and proper disposal of all existing sign luminaires to include all brackets, wire conduit, and other associated hardware. As a complimentary effort required contract work will also include identifying the electrical power load center supplying power to each overhead sign structure, determining the safest point of disconnect that would eliminate voltage to the old sign structure wiring without impacting the operations of other existing overhead luminaires and/or high mast lighting, and proper electric termination of any wiring that is disconnected so as to ensure safety and compliance with the National Electrical Code. Nomenclature utilized on all new Guide Sign Panels shall match that of existing signs that are being replaced. All work is to be performed at night. Mobilization and Maintenance of Traffic including Traffic Control Officers will be incidental to the other items of the Bid Proposal.

Experience in Overhead Signs form number 850-070-03 is required to be submitted with the bid documents.

Call Order: 010 Proposal: E3T80

ALT	Item	Description	Unit	Quantity
Section 0001 SIGNS (GROUND SIGNS OVER 30 SQ FT)(UN)				
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	6.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	16.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	15.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	20.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	15.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	11.000
	0700- 3-209	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 401-500 SF	EA	3.000
	0700- 3-624	SIGN PANEL, REMOVE, UP TO 50 SF WITH LIGHTING	EA	22.000
	0700- 3-625	SIGN PANEL, REMOVE, 51-100 SF WITH LIGHTING	EA	15.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	20.000
	0700- 3-627	SIGN PANEL, REMOVE PANEL, 201-300 SF WITH LIGHTING	EA	15.000
	0700- 3-628	SIGN PANEL, REMOVE PANEL, 301-400 SF WITH LIGHTING	EA	11.000
	0700- 3-629	SIGN PANEL, REMOVE PANEL, 401-500 SF WITH LIGHTING	EA	3.000