

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03200813	Call Order: 004	Proposal: E3T96	District:03
Counties:	WALTON			
Road Name:	SR 83 (US 331)			
Limits:	60040000			
Project(s):	4453581G201(*)	Federal Aid No: E191121E		
Total Roadway Length:	6.360 Miles	Contract Days:	90	
Total Bridge Length:	0.000 Miles	Letting Date:	08/13/20	
Total Proposal Length:	6.360 Miles	Contract Execution Days:	5	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	45 Day Other	
Proposal Budget Estimate:	\$1,088,772.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of permanently replacing the Coastal Shore riprap; displaced by Hurricane Michael at the North-West Causeway at the Northbound Structure No. 600224 Choctawhatchee Relief; plus Clyde B Wells Bridge NOS. 600108 and 600110 on State Road 83 (US 331) from South of Clyde B Wells Bridge to North of Relief Bridge in Walton County. Other incidental work includes but is not limited to, minor drainage, sidewalk repair and replacement and minor lighting repair.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

FHWA 1273 and Davis Bacon Wage Rates are applicable for this Contract

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 004 Proposal: E3T96

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (4453581G201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (4453581G201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,210.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	11,584.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,620.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	85.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	97.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	170.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	170.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	3,328.000
	0110- 1- 1	CLEARING & GRUBBING (4453581G201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	338.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	3,812.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	13.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	308.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	29.000
	0530- 3- 5	RIPRAP- RUBBLE, COASTAL SHORE- LARGE BOULDERS	TN	1,302.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,325.000
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	60.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	20.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	432.000
	0715- 7- 31	LOAD CENTER, RELOCATE, SECONDARY VOLTAGE	EA	2.000