

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 03201113      Call Order: 003      Proposal: E3T37      District:03

Counties: LEON

Road Name: SR 363/61 S MONROE ST - RESURFACING

Limits: 55040000

Project(s): 44154715201(\*)      Federal Aid No: N/A

Project(s): 44154715202      Federal Aid No: N/A

Project(s): 44154715203      Federal Aid No: N/A

Project(s): 44154715204      Federal Aid No: N/A

Total Roadway Length:	9.536 Miles	Contract Days:	150
Total Bridge Length:	0.000 Miles	Letting Date:	11/13/20
Total Proposal Length:	9.536 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$2,220,196.00

Please read the full advertisement

**Description:**

The Improvements under this District Contract consist of 441547-1-52-01, Milling & Resurfacing, Minor Drainage, Sidewalk/Curb Ramps, Curb & Gutter S&PMs, and Signalization on SR 363/61 S Monroe St from E Paul Russell Rd to Perkins St in Leon County, 441547-1-52-02, City of Tallahassee Patterned Pavement Agreement; 441547-1-52-03, City of Tallahassee Water and Sewer Adjustments; 441547-1-52-04, City of Tallahassee Gas Valve Adjustments.

PRE-QUALIFICATION REQUIRED TO BID ON THIS PROJECT

**Call Order: 003 Proposal: E3T37**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44154715201)	LS	1.000
	0101- 1-	MOBILIZATION (44154715202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44154715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44154715202)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	15.500
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	88.000
	0102- 60-	WORK ZONE SIGN	ED	13,010.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	11,442.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	39,900.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	80.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	188.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	600.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	600.000
	0104- 10- 3	SEDIMENT BARRIER	LF	28.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	49.000
	0107- 1-	LITTER REMOVAL	AC	22.420
	0107- 2-	MOWING	AC	8.620

**Call Order: 003 Proposal: E3T37**

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (44154715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,062.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	47.000
	0327- 70- 2	MILLING EXIST ASPH PAVT, 3 1/2" AVG DEPTH	SY	746.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	50,198.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	61.600
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	5,527.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	0.100
	0425- 1-561	INLETS, DT BOT, TYPE F, <10'	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	10.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	29.000
	0425- 6-	VALVE BOXES, ADJUST	EA	58.000
	0425- 8-	DRAINAGE STRUCTURES, MISCELLANEOUS, ADJUST	EA	1.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	20.000
	0515- 4- 1	BULLET RAIL, SINGLE RAIL	LF	15.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,865.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	45.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,390.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,300.000
	0523- 1-	PATTERNED PAVEMENT, VEHICULAR AREAS	SY	515.000
	0527- 2-	DETECTABLE WARNINGS	SF	660.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	649.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	2.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.241
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.048
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	4,033.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	32.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	637.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.920
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.212
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	37.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.086
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	125.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.227
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.222
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44154715201)	LS	1.000

**Call Order: 003 Proposal: E3T37**

ALT	Item	Description	Unit	Quantity
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44154715202)	LS	1.000
	1050- 15-004	UTILITY PIPE, ADJUST/MODIFY, 8 - 19.9"	LF	30.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	33.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	17.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	9.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	10.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	43.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	1.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	80.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	12.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	133.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44154715201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,033.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	32.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	637.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.285
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	37.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	125.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.222
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,539.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	34.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	34.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.241
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.048
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",1C-30 SKIP OR 3-9 LANE DROP	GM	1.920
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.086
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.227
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	520.000
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	403.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	40.000

**Call Order: 003 Proposal: E3T37**

ALT	Item	Description	Unit	Quantity
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	4.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	24.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	28.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0650- 2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	6.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	28.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	24.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	28.000
	0665- 1- 50	PEDESTRIAN DETECTOR, ADJUST/MODIFY ON EXISTING POLE	EA	1.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	24.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	5.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000