



## Florida Department of Transportation

RON DESANTIS  
GOVERNOR

1074 Hwy 90  
Chipley, Florida 32428

KEVIN J. THIBAUT, P.E.  
SECRETARY

January 10, 2020

### ADDENDUM NO. 2

**To: ALL PROPOSAL HOLDERS**  
**FINANCIAL ITEM NUMBER: 42214327272**  
**CONTRACT NUMBER: E3T47**  
**DESCRIPTION: The improvements under this Contract consist of milling and resurfacing of pavement markings along SR 30 (US98) in Walton County.**

---

BIDS TO BE RECEIVED: January 16, 2020

If you are a PROPOSAL HOLDER, this is your authorization to make the following changes to the plans and specification packages you now have for the subject project:

- **Specifications Appendix A: Locations, page 26 has been revised and replaced with the attached Appendix A: Locations, Page 26**

Please use this revision when preparing your bid.

Sealed bids will be received until 2:00 p.m. local time on January 16, 2020 in the District Three Procurement Services Conference Room, Room 230, Administration Building, 1074 Highway 90, Chipley, Florida.

### AMENDMENT NOTIFICATION

If you are a PROPOSAL HOLDER, please go to the CPP Online Ordering System at <https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/> to download Amendment No. 2, file E3T47.002.

Also all PROPOSAL HOLDERS please acknowledge receipt of the addendum under the Acknowledgement of Amendments tab on your electronic bid.

If you have any further questions please contact Amanda Mauldin by phone at (850) 330-1364 or by email at [roland.ybarra@dot.state.fl.us](mailto:roland.ybarra@dot.state.fl.us).

Sincerely,

Steve Thames  
District Contracts Manager

ST:ry

c.c. Tim Hendrix, Heath Riley, Richard Yates, Jared Kirkland, file

**APPENDIX A: LOCATIONS**

County	State Road	Sites
Walton	30	<p><b>1.700 miles west of Water Sound Parkway (Mile Post 22.556)</b></p> <ul style="list-style-type: none"> <li>• Westbound Lane-1 (600 LF) and Westbound Lane-2 (600 LF) (this also includes the paved shoulder area), Mill 2 ½ inch and resurface with 1 ¾ inch of SP 12.5 Traffic Level C at 192.5 lb/sy spread rate and ¾ inch of FC 5 Traffic Level C at 80.0 lb/sy spread rate</li> </ul>
Walton	30	<p><b>J.D. Miller Road (Mile Post 12.660)</b></p> <ul style="list-style-type: none"> <li>• Eastbound left turn lane and Westbound left turn lane including median opening, Mill 1 ¼ inch and resurfaced with 1 ¼ inch of FC 9.5 Traffic Level C at 137.5 lb/sy spread rate</li> </ul>
Walton	30	<p><b>County Highway 83 South (Mile Post 12.144)</b></p> <ul style="list-style-type: none"> <li>• Eastbound left lane and Westbound left lane including median opening, Mill 1 ¼ inch and resurfaced with 1 ¼ inch of FC 9.5 Traffic Level C at 137.5 lb/sy spread rate</li> <li>• Eastbound right turn lane and Westbound right turn lane, Mill 1 ½ inch and resurfaced with 1 ¼ inch of FC 9.5 Traffic Level C at 137.5 lb/sy spread rate</li> <li>• Westbound Lane-1 (300 LF), Mill 1 inch and replace with FC 5 at 107 lb/sy spread rate</li> </ul>
Walton	30	<p><b>Bishop Tolbert Road/Thomason Road Intersection (Mile Post 9.105)</b></p> <ul style="list-style-type: none"> <li>• Eastbound left turn lane and Westbound left turn lane including median opening, Mill 1 ¼ inch and resurfaced with 1 ¼ inch of FC 9.5 Traffic Level C at 137.5 lb/sy spread rate.</li> <li>• Eastbound right turn lane, Mill 1 ½ inch and resurfaced with 1 ¼ inch of FC 9.5 Traffic Level C at 137.5 lb/sy spread rate</li> <li>• Westbound Lane-1 (left lane) (600 LF), Mill 1 ¼ inch and resurfaced with 1 ¼ inch of FC 9.5 Traffic Level C at 137.5 lb/sy spread rate</li> </ul>
Walton	30	<p><b>0.210 miles east of Don Bishop (Mile Post 8.122)</b></p> <ul style="list-style-type: none"> <li>• Eastbound left turn lane to pavement joint at median opening, Mill 1 ¼ inch and resurfaced with 1 ¼ inch of FC 9.5 Traffic Level C at 137.5 lb/sy spread rate.</li> </ul>