

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	03200109	Call Order: 003	Proposal: E3T48-R0	District:03
Counties:	LEON			
Road Name:	MIDWAY OPERATIONS MAINTENANCE - CONCRETE REPAIR			
Limits:	Midpoint			
Project(s):	42215127214(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	Thru 12-31-2020	
Total Bridge Length:	0.000 Miles	Letting Date:	01/09/20	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 days	
Proposal Budget Estimate:	\$300,000.00			

Please read the full advertisement

**Description:**

The work under this Push-Button Contract consists of night-time removal, replacement and/or repairs of driveways, sidewalks, detectable warnings, curbs, gutters, inlet tops, and manholes located in urban Leon County as described in the appendices. Other services required to achieve this work include Maintenance of Traffic, adjusting utility features (e.g. manhole rings, water meter boxes, valve risers, etc.), providing erosion control, borrow material or hot-mix asphalt, maintaining pedestrian and driveway access, sodding and watering disturbed areas. Coordinate work with owners of nearby affected utilities. Mobilization is incidental to other items listed.

This Contract has a budgetary ceiling of \$300,000.00.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 003 Proposal: E3T48-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 TRAFFIC CONTROL DEVICES CONTROL (MH)</b>				
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	250.000
	0102- 60-	WORK ZONE SIGN	ED	500.000
	0102- 61-	BUSINESS SIGN	EA	12.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,000.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	1,000.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	24.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	10.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	12.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	500.000
	0104- 10- 3	SEDIMENT BARRIER	LF	200.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,130.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	300.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	500.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	110.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	20.000
	0425- 5-	MANHOLE, ADJUST	EA	50.000
	0425- 6-	VALVE BOXES, ADJUST	EA	5.000
	0425- 15- 43	INLET TOP, REPAIR,CURB INLET- WALKING SURFACE ONLY	EA	40.000
	0425- 15- 44	INLET TOP, REPAIR,CURB INLET- CURB FACE ONLY	EA	80.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	40.000
	0515- 1- 41	PIPE HANDRAIL - GUIDERAIL, RELOCATE, STEEL	LF	40.000
	0515- 1- 42	PIPE HANDRAIL - GUIDERAIL, RELOCATE, ALUMINUM	LF	40.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	40.000
	0515- 2-500	PEDESTRIAN / BICYCLE RAILING, RELOCATE	LF	40.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	50.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	300.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	10.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,250.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	800.000
	0527- 2-	DETECTABLE WARNINGS	SF	500.000
	E102- 10-	OFF-DUTY LAW ENFORCEMENT OFFICER	MH	20.000
	E102-100-	MOT MAINTENANCE SERVICES	HR	200.000
	E110- 70-	REMOVAL OF FLEXIBLE PAVEMENT	SY	100.000
	E425- 73- 7	MANHOLE FRAME & COVER	EA	10.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	34.000
	E575- 1-	SODDING	SY	1,500.000