

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	03200709	Call Order: 002	Proposal: E3T25	District:03
Counties:	GADSDEN			
Road Name:	SR 63 (US 27)			
Limits:	50020000			
Project(s):	44154615201(*)	Federal Aid No: N/A		
Total Roadway Length:	6.076 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	07/09/20	
Total Proposal Length:	6.076 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$2,348,822.00			

Please read the full advertisement

**Description:**

The Improvements under this District Contract consist of resurfacing SR 63 (US 27) S Main St from S of SR 159 to CR 159A Potter Woodberry Rd in Gadsden County. Existing travel lanes, auxiliary lanes, median crossovers, and paved shoulders will be resurfaced. Some minor widening, drainage work, and a median closure at Hinson Main Street will also be included. Finally, improvements will be made to signals, sidewalks, curb ramps, cross walks, and other pedestrian features.  
 The summary of pay items for this project is listed in the Plans.

PREQUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

**Call Order: 002 Proposal: E3T25**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44154615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44154615201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	56.000
	0102- 60-	WORK ZONE SIGN	ED	10,200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	40,600.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	518.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	240.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	120.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	240.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	240.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	240.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	240.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,542.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	99.000
	0107- 1-	LITTER REMOVAL	AC	50.190
	0107- 2-	MOWING	AC	46.360
	0110- 1- 1	CLEARING & GRUBBING (44154615201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	847.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	304.800

**Call Order: 002 Proposal: E3T25**

ALT	Item	Description	Unit	Quantity
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44154615201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	380.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	354.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	111,100.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	36.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	9,202.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	14.100
	0425- 1-335	INLETS, CURB, TYPE P-3, PARTIAL	EA	14.000
	0425- 1-345	INLETS, CURB, TYPE P-4, PARTIAL	EA	14.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	2.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	1.000
	0425- 1-481	INLETS, CURB, TYPE 8, <10'	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-545	INLETS, DITCH BOTTOM, TYPE D, PARTIAL	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	8.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	7.000
	0425- 6-	VALVE BOXES, ADJUST	EA	14.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	68.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	98.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,160.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	187.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	253.000
	0527- 2-	DETECTABLE WARNINGS	SF	56.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	406.000
	0536- 73-	GUARDRAIL REMOVAL	LF	238.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0570- 1- 1	PERFORMANCE TURF	SY	2,701.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,585.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	6.196
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.197
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,525.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	115.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	543.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	6.157
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	29.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.434
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	226.000

**Call Order: 002 Proposal: E3T25**

ALT	Item	Description	Unit	Quantity
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.081
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44154615201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	16.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	39.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	26.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	46.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	436.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44154615201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,525.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	115.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	543.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	29.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	226.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.081
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	700.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	6.196
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.197
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",1C-30 SKIP OR 3-9 LANE DROP	GM	6.157
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.434
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	96.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	7.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	3.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	2.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	4.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	10.000

**Call Order: 002 Proposal: E3T25**

ALT	Item	Description	Unit	Quantity
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	4.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	10.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	14.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	14.000