

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03200709	Call Order: 004	Proposal: E3T53	District:03
Counties:	HOLMES			
Road Name:	ROAD RECONSTRUCTION - 2 LANE			
Limits:	52002000			
Project(s):	42187835201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.064 Miles	Contract Days:	60	
Total Bridge Length:	0.000 Miles	Letting Date:	07/09/20	
Total Proposal Length:	0.064 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$258,312.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of reconstruction of all three eastbound travel lanes and auxiliary lane on SR 8 (I-10) Eastbound Roadway West of Sandy Creek Bridge No. 520047 in Holmes County. The summary of pay items for this project is listed in the Plans.

PREQUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 004 Proposal: E3T53

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (42187835201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42187835201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,150.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,465.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	39.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	5.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	249.000
	0102-115-	TYPE III BARRICADE	ED	56.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	78.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	78.000
	0104- 10- 3	SEDIMENT BARRIER	LF	697.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	1.910
	0107- 2-	MOWING	AC	1.530
	0110- 1- 1	CLEARING & GRUBBING (42187835201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	320.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	313.000
	0285-745-	OPTIONAL BASE- GRADED AGGREGATE, 20" FOR PROJECT 421878-3-52-01	SY	320.000
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	79.200
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	13.300
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.015
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.031
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.015
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42187835201)	LS	1.000
Section 0002 Signing				
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42187835201)	LS	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.015
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.031
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.015