

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03200611	Call Order: 001	Proposal: E3T35	District:03
Counties:	ESCAMBIA			
Road Name:	BRIDGE-REPAIR/REHABILITATION			
Limits:	48260000			
Project(s):	44291315201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.444 Miles	Contract Days:	90	
Total Bridge Length:	0.222 Miles	Letting Date:	06/11/20	
Total Proposal Length:	0.666 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 days Other	

Proposal Budget Estimate: \$1,258,634.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of replacing the existing western slab for the SR 8 (I-10) eastbound bridge over Perdido River (Bridge No. 480081). Also includes milling and resurfacing, asphalt pavement reconstruction, guardrail replacement, and pavement markings in Escambia County.

The summary of pay items for this project is listed in the Plans.

Pre-Qualification is Required to Bid on this Project.

Mandatory Pre-Conference has been scheduled for this project. Location: Florida Department of Transportation, 1074 Hwy 90 East, Chipley, Florida 32428. Date and Time: May 13, 2020, 10:00 A.M. Local Time Place: Design Conference Room.

Proposals (Bidding Documents) will be issued only to the prospective bidders who have attended the pre-bid meeting and met the Florida Department of Transportation qualifications for this project. Prospective bidders ordering bid documents prior to the pre-bid meeting will be given access to download the bid documents within 24 hours after the pre-bid meeting. Those prospective bidders ordering the documents after the pre-bid meeting will need to contact the office advertising the project to confirm attendance and receive access to download the bid documents. Please contact the office at least two working days prior to the deadline for obtaining bid documents to allow time for processing.

Call Order: 001 Proposal: E3T35

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 9-	BRIDGE DECK GROOVING & PLANING, DECK 8.5" AND GREATER	SY	134.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	2.500
	0400-153-	NON SHRINK GROUT, F&I, MISCELLANEOUS- STRUCTURES REHAB	CF	155.000
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	100.000
	0413-151-	METHACRYLATE MONOMER	GA	12.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	1,200.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	40.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, Poured JOINT WITH BACKER ROD	LF	41.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	3.000
	0460- 1- 15	STRUCTURAL STEEL - REHABILITATION, MISCELLANEOUS	LB	13,355.000
	0521- 5- 46	CONCRETE TRAFFIC RAILING- BRIDGE, 32" F-SHAPE, PROJECT 442913-1-52-01	LF	60.000
	0916-400- 4	PRECAST APPROACH SLAB UNIT, PROJECT 442913-1-52-01	SF	1,293.000

Call Order: 001 Proposal: E3T35

ALT	Item	Description	Unit	Quantity
	0918-349- 7	ULTRA HIGH PERFORMANCE CONCRETE- UHPC, PROJECT 442913-1-52-01	CY	3.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44291315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44291315201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (44291315201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (44291315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	600.000
	0102- 60-	WORK ZONE SIGN	ED	2,220.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	1,908.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	1,032.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	22,504.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	92.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	2,499.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	3.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	188.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	180.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	180.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	1.543
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.772
	0102-913-100	REMOVABLE TAPE, WHITE, SOLID 18" CHEVRON, PROJECT 442913-1-52-01	LF	63.000
	0102-913-101	REMOVABLE TAPE, YELLOW, SOLID 18" CHEVRON, PROJECT 442913-1-52-01	LF	52.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,136.000
	0110- 1- 1	CLEARING & GRUBBING (44291315201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	115.000
	0120- 1-	REGULAR EXCAVATION	CY	71.200
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	277.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	144.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	134.000
	0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY	2,117.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	3,014.000
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	213.400
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	131.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	64.700
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,270.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,303.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.406
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,615.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.207
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.207

Call Order: 001 Proposal: E3T35

ALT	Item	Description	Unit	Quantity
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.207
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44291315201)	LS	1.000
Section 0003 Signing				
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44291315201)	LS	1.000
	0711- 14-004	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" DIAGONAL, PROJECT 442913-1-52-01	LF	137.000
	0711- 14-005	THERMOPLASTIC, PREFORMED, YELLOW, SOLID, 12" DIAGONAL, PROJECT 442913-1-52-01	LF	100.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.207
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.207
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.207
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.231
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.231
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.231
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.231