

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting:	03200611	Call Order: 002	Proposal: E3T90	District:03
Counties:	SANTA ROSA			
Road Name:	MILTON MAINTENANCE - THERMOPLASTIC			
Limits:	57002000			
Project(s):	42214227277(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	06/11/20	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$933,000.00			

Please read the full advertisement

Description:

The Improvements under this Site-Specific contract consist of removal and replacement of thermoplastic pavement markings, including solid and skip lines, guide lines, messages, arrows, symbols, stops bars, crosswalks, bicycle symbols, rumble strips and gore areas as well as reflective pavement markers on SR 89 By-Pass, SR 89 North and SR 87 North in Santa Rosa County, at locations shown in the Appendices. All work will be performed at night and a Traffic Control Officer will be required for all Work Zones. Maintenance of Traffic, Mobilization and Traffic Control Officers are incidental to pay items.

A Contractor Experience Form (850-070-06), Experience in Pavement Markings, is required to be submitted with bid.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 002 Proposal: E3T90**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)</b>				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	4.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	1.389
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	11,408.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,665.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	3,043.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.118
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	37.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	466.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,974.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.100
	0711- 13-111	THERMOPLASTIC, HOT SPRAY, WHITE, SOLID, 6" MAINTENANCE USE ONLY	NM	21.695
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	151.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	151.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	70.941
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",1C-30 SKIP OR 3-9 LANE DROP	GM	20.284
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	29.585
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	19.879
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	275,347.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	9,752.000