

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03200312 Call Order: 009 Proposal: E3T66 District:03

Counties: BAY

Road Name: - EMERGENCY OPERATIONS

Limits: 46010100

Project(s): 4450184H201(*) Federal Aid No: E191129E

Total Roadway Length:	0.683 Miles	Contract Days:	90
Total Bridge Length:	0.000 Miles	Letting Date:	03/12/20
Total Proposal Length:	0.683 Miles	Contract Execution Days:	5
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$234,813.00

Please read the full advertisement

Description:

The Improvements under this District Contract FPID 445018-4-H2-01 consist of permanent replacement of all aesthetic (pier up-lights) and maintenance lights located on the underside of the bridge, on piers and on pier footings with new LED light fixtures on SR 30 (US98) Hathaway Bridge, Bridge Nos. 460112 & 460113 located in Bay County. Also included will be removal and permanent replacement of all surface mounted conduit associated with bridge pier and maintenance lighting and installation of new surface mounted conduit where required for new conductors. Permanent replacement of conductor wiring from the new fixtures up to junction boxes located within (inside) the segment box of the Bridge No. 460113 (westbound SR 30) above.

FHWA 1273 and Davis Bacon Wage Rates are applicable for this Contract

Call Order: 009 Proposal: E3T66

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (4450184H201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (4450184H201)	LS	1.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	990.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	720.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	200.000
	0630- 2- 65	CONDUIT, REMOVE, BRIDGE MOUNT	LF	200.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	20.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	3,535.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,230.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	4,065.000
	0715- 11- 21	LUMINAIRE- PIER LIGHT, F&I, PROJECT 445018-4-H2-01	EA	26.000
	0715- 11- 23	LUMINAIRE- MAINTENANCE LIGHTS, F&I, PROJECT 445018-4-H2-01	EA	9.000
	0715- 21- 5	LUMINAIRE, PIER LIGHTS, REMOVE	EA	19.000
	0715- 21- 7	LUMINAIRE, MAINTENANCE LIGHTS, REMOVE	EA	9.000