

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03200514	Call Order: 003	Proposal: E3T85	District:03
Counties:	JACKSON, WASHINGTON			
Road Name:	MARIANNA MAINTENANCE - RPM & THERMOPLASTIC			
Limits:	Midpoint			
Project(s):	42212227217(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	05/14/20	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$1,350,000.00			

Please read the full advertisement

Description:

The Improvements under this Site-Specific Contract consist of the removal and/or placement of reflective pavement markers and thermoplastic pavement markings (striping, symbols, arrows, messages) on various roadways along SR 69, SR 71, & SR 277 in Jackson & Washington Counties at locations shown in the Appendices. All items removed shall be replaced by the end of the work day. Mobilization and Maintenance of Traffic shall be incidental to the bid items listed.

A Contractor Experience in Pavement Markings Form, No. 850-070-06 is required to be submitted with bid.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 003 Proposal: E3T85

ALT	Item	Description	Unit	Quantity
Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)				
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	12.090
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,655.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	3,100.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	2,290.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.690
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	22.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	79.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	20.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	3,180.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.230
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	270.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	5.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	109.920
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	1.620
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	57.120
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	38.740
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	570,519.000
E706-	1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	14,810.000