

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 03200910 Call Order: 001 Proposal: E3T52 District:03  
 Counties: ESCAMBIA  
 Road Name: SR 292 SORRENTO - INTERSECTION IMPROVEMENT  
 Limits: 48050000  
 Project(s): 43996415201(\*) Federal Aid No: N/A  
 Project(s): 43996415202 Federal Aid No: N/A  
 Project(s): 43996415601 Federal Aid No: N/A  
 Total Roadway Length: 1.410 Miles Contract Days: 330  
 Total Bridge Length: 0.000 Miles Letting Date: 09/10/20  
 Total Proposal Length: 1.410 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Day Standard  
 Proposal Budget Estimate: \$2,517,999.00

Please read the full advertisement

**Description:**

The Improvements under this District Contract consist of widening, milling and resurfacing, drainage, signing and pavement markings, signalization, and utilities (FPID 439964-1-52-02 and FPID 439964-1-56-01), along SR 292 Sorrento @ CR 292A Innerarity Point Intersection in Escambia County. Prequalification is required to bid on this project.

**Call Order: 001 Proposal: E3T52**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43996415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43996415201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43996415201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43996415201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	83.700
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43996415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	21,875.000
	0102- 61-	BUSINESS SIGN	EA	9.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	708.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	824.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	43,750.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	11,490.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	660.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	107.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,376.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	330.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	330.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	26.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,179.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	7.000

**Call Order: 001 Proposal: E3T52**

ALT	Item	Description	Unit	Quantity
	0107- 1-	LITTER REMOVAL	AC	9.790
	0107- 2-	MOWING	AC	9.790
	0110- 1- 1	CLEARING & GRUBBING (43996415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	999.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	471.400
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43996415201)	LS	1.000
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	231.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	1,661.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	37.500
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	6,419.000
	0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY	445.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	337.900
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	602.100
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	3.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	2.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	3.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	70.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	40.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	585.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	244.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	1.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	231.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,659.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	99.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	18.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	706.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	486.000
	0527- 2-	DETECTABLE WARNINGS	SF	230.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	26.400
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,671.000
	0654- 2- 22	RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR POWERED, COMPLETE SIGN ASSEMBLY- BACK TO BACK	AS	4.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.095
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	80.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	338.000

**Call Order: 001 Proposal: E3T52**

ALT	Item	Description	Unit	Quantity
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.180
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	3.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.700
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	50.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43996415201)	LS	1.000
	1050- 61-124	UTILITY PIPE- STEEL, FURNISH & INSTALL, CASING, 24"	LF	12.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	8.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	10.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	2.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43996415201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.068
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	907.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	121.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	181.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.233
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	13.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	12.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	40.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.065
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	545.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	7.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	7.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.784
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.564
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	975.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	565.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	30.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	30.000

**Call Order: 001 Proposal: E3T52**

ALT	Item	Description	Unit	Quantity
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	8.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	4.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	2.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	3.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	8.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	4.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	8.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	10.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	2.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	2.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	4.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	6.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	4.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	1.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0684- 6- 12	WIRELESS COMMUNICATION DEVICE, FURNISH & INSTALL ETHERNET SUBSCRIBER UNIT	EA	1.000
	0685- 1- 14	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION WITH CABINET	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000
<b>Section 0004 Utilities</b>				
	0425- 6-	VALVE BOXES, ADJUST	EA	4.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43996415202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43996415601)	LS	1.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	970.000
	1050- 18-003	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 5- 7.9"	LF	105.000

**Call Order: 001 Proposal: E3T52**

ALT	Item	Description	Unit	Quantity
	1050- 18-004	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 8-19.9"	LF	1,910.000
	1050- 31-206	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	100.000
	1050- 31-208	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 8"	LF	20.000
	1050- 31-210	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 10"	LF	20.000
	1050- 31-212	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 12"	LF	90.000
	1050- 31-216	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 16"	LF	1,090.000
	1050- 51-224	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 24"	LF	255.000
	1050- 61-124	UTILITY PIPE- STEEL, FURNISH & INSTALL, CASING, 24"	LF	106.000
	1050- 61-136	UTILITY PIPE- STEEL, FURNISH & INSTALL, CASING, 36"	LF	95.000
	1055- 51-108	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 8"	EA	3.000
	1055- 51-110	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 10"	EA	1.000
	1055- 51-112	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 12"	EA	4.000
	1055- 51-116	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 16"	EA	13.000
	1055- 51-124	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 24"	EA	1.000
	1055- 51-208	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL TEE, 8"	EA	1.000
	1055- 51-212	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL TEE, 12"	EA	1.000
	1055- 51-216	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL TEE, 16"	EA	4.000
	1055- 51-224	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL TEE, 24"	EA	3.000
	1055- 51-312	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 12"	EA	1.000
	1055- 51-316	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 16"	EA	1.000
	1055- 51-324	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 24"	EA	2.000
	1060- 15-	UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	EA	1.000
	1080- 21-500	UTILITY FIXTURE, VALVE/METER BOX, ADJUST	EA	4.000
	1080- 23-106	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 6"	EA	3.000
	1080- 23-108	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 8"	EA	2.000
	1080- 23-110	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 10"	EA	2.000
	1080- 23-112	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 12"	EA	2.000
	1080- 23-116	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 16"	EA	1.000
	1080- 23-124	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 24"	EA	1.000

**Call Order: 001 Proposal: E3T52**

ALT	Item	Description	Unit	Quantity
	1080- 24-108	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 8"	EA	1.000
	1080- 24-110	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 10"	EA	1.000
	1080- 24-112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	2.000
	1080- 24-116	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 16"	EA	8.000
	1080- 24-124	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 24"	EA	6.000
	1644-112- 06	FIRE HYDRANT, F&I, STANDARD, 2 HOSE, 6"	EA	2.000
	1644-900-	FIRE HYDRANT, REMOVE	EA	2.000