

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03210812 Call Order: 003 Proposal: E3U13 District:03
Counties: CALHOUN
Road Name: - BRIDGE-REPAIR/REHABILITATION
Limits: 47010000
Project(s): 42357755201(*) Federal Aid No: N/A
Total Roadway Length: 3.194 Miles Contract Days: 180
Total Bridge Length: 1.584 Miles Letting Date: 08/12/21
Total Proposal Length: 4.778 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 15 Day Acquis.
Proposal Budget Estimate: \$2,043,791.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of SR 20 over Apalachicola River, EB Bridge No. 470052, Deck Sealing, Expansion Joint Replacement and other incidental work in Calhoun County, Florida (47010).

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 003 Proposal: E3U13

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 32-	CONCRETE FOR JOINT REPAIR	CY	2.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	380.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	3,750.000
	0413-151-	METHACRYLATE MONOMER	GA	4,008.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	400,720.000
	0413-155-101	RESTORE SPALLED AREAS FOR SEALING CONCRETE BRIDGE DECKS, PROJECT 423577-5-52-01	CF	30.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	50.000
	0458- 1- 22	BRIDGE DECK EXPANSION JOINT, REHABILITATION, STRIP SEAL	LF	1,250.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (42357755201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42357755201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,710.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	20,340.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	194.000
	0102-115-	TYPE III BARRICADE	ED	40.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	1.548
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	1.548
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	1.548
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42357755201)	LS	1.000
Section 0003 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	217.000
	0918-712- 30	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SOLID 6", PROJECT 423577-5-52-01	GM	1.548
	0918-712- 31	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SKIP/DOTTED 6", PROJECT 423577-5-52-01	GM	1.548
	0918-712- 32	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, SOLID 6", PROJECT 423577-5-52-01	GM	1.548