

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting: 03211209      Call Order: 003      Proposal: E3V29-R0      District:03  
Counties: JACKSON, WASHINGTON  
Road Name: MARIANNA MAINTENANCE - WDD CONCRETE REMOVE AND REPLACE  
Limits: Midpoint  
Project(s): 42212227202(\*)      Federal Aid No: N/A  
Total Roadway Length: 0.000 Miles      Contract Days: Thru 12/31/2022  
Total Bridge Length: 0.000 Miles      Letting Date: 12/09/21  
Total Proposal Length: 0.000 Miles      Contract Execution Days: 10  
Special Start Date: N/A  
Aquis/Flexible Start Time:  
Proposal Budget Estimate: \$300,000.00

Please read the full advertisement

**Description:**

The improvements in this Work Document-Driven Contract consists of miscellaneous concrete repair to be performed on a call out basis in Jackson and Washington Counties. The work will consist primarily of the removal and replacement of damaged sidewalk, curb and gutter, ditch pavement, driveways, inlet tops, curb ramps and mitered end slabs. Work may include miscellaneous asphalt repair and seeding and sodding around completed areas. Maintenance of Traffic and Mobilization will be incidental to the pay items provided. This contract has a budgetary ceiling of \$300,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 003 Proposal: E3V29-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 SODDING (SY)</b>				
	0104- 10- 3	SEDIMENT BARRIER	LF	200.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	500.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1.000
	0425- 1-315	INLETS, CURB TYPE P-1, PARTIAL	EA	1.000
	0425- 1-325	INLETS, CURB, TYPE P-2, PARTIAL	EA	1.000
	0425- 1-525	INLETS, DITCH BOTTOM, TYPE C, PARTIAL	EA	1.000
	0425- 1-555	INLETS, DT BOT, TYPE E, PARTIAL	EA	1.000
	0425- 15- 41	INLET TOP, REPAIR, CURB INLET	EA	5.000
	0425- 15- 42	INLET TOP, REPAIR, DITCH BOTTOM INLET	EA	7.000
	0430-990-	MITERED END SECT, REPLACE GRATE	EA	15.000
	0430-991- 1	MITERED END SECT, REPLACE SLAB- MAINTENANCE USE ONLY	CY	114.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	20.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	20.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	500.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	100.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	1,500.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	25.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	25.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	25.000
	0524- 2- 1	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 3"	SY	50.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	50.000
	0527- 2-	DETECTABLE WARNINGS	SF	20.000
	E110- 2-	CLEARING & GRUBBING	AC	1.000
	E570- 2-	SEED & MULCH	SY	450.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	25.000
	E575- 1-	SODDING	SY	375.000