

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03210708 Call Order: 001 Proposal: E3T34 District:03
 Counties: FRANKLIN
 Road Name: - BRIDGE-REPAIR/REHABILITATION
 Limits: 49030000
 Project(s): 44547215201(*) Federal Aid No: N/A
 Total Roadway Length: 0.164 Miles Contract Days: 200
 Total Bridge Length: 0.163 Miles Letting Date: 07/08/21
 Total Proposal Length: 0.327 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 60 Day Acquis.

Proposal Budget Estimate: \$3,249,105.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of the installation of integral pile jackets, pile protection jacket systems, restore spalled areas in the deck, deck sealing and other incidental construction for SR 377 (US 319) over Ochlockonee River, Bridge No. 490028 in Franklin County.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 001 Proposal: E3T34

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	5.000
	0413-151-	METHACRYLATE MONOMER	GA	376.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	37,519.000
	0457- 1- 12	STANDARD INTEGRAL PILE JACKET, NON-STRUCTURAL, 16.1 to 30.0"	LF	634.000
	0457- 1- 22	STANDARD INTEGRAL PILE JACKET, STRUCTURAL, 16.1 to 30.0"	LF	208.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44547215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44547215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,000.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	8,612.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	428.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	200.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,980.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44547215201)	LS	1.000
Section 0003 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	21.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.328
	0713-103-231	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES	GM	0.164