

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03210708	Call Order: 002	Proposal: E3U12	District:03
Counties:	JACKSON			
Road Name:	- RESURFACING			
Limits:	53010000			
Project(s):	44365725201(*)	Federal Aid No: N/A		
Total Roadway Length:	4.390 Miles	Contract Days:	100	
Total Bridge Length:	0.000 Miles	Letting Date:	07/08/21	
Total Proposal Length:	4.390 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Day Standard	
Proposal Budget Estimate:		\$2,808,633.00		

Please read the full advertisement

Description:

The Improvements under this District Contract consist of milling and resurfacing SR 10 (US 90) from Washington CL to concrete pavement W of SR 75 (US 231) in Jackson County. Other items of work include ditch grading, drainage and signing and pavement marking.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 002 Proposal: E3U12

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44365725201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44365725201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	133.000
	0102- 60-	WORK ZONE SIGN	ED	2,300.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	17,400.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	214.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	100.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,082.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	200.000
	0107- 1-	LITTER REMOVAL	AC	184.450
	0107- 2-	MOWING	AC	101.970
	0110- 1- 1	CLEARING & GRUBBING (44365725201)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	59.100
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	301.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	60,990.000
	0327- 70- 16	MILLING EXISTING ASPHALT PAVEMENT, 1/2" AVG DEPTH	SY	1,058.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	25,412.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	4,193.000
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	6,037.600
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	691.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	252.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	36.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	16.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	13,680.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	649.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.639
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.182
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	8.648
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44365725201)	LS	1.000
Section 0002 Signing				
	0701- 18-101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	8.639
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	649.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44365725201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	150.000
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.591
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	4.324