

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 03210708	Call Order: 004	Proposal: E3U25	District:03
Counties: GADSDEN			
Road Name: RESURFACING			
Limits: 50040000			
Project(s): 44364215201(*)	Federal Aid No: N/A		
Total Roadway Length: 7.157 Miles	Contract Days: 160		
Total Bridge Length: 0.000 Miles	Letting Date: 07/08/21		
Total Proposal Length: 7.157 Miles	Contract Execution Days: 10		
	Special Start Date: N/A		
	Aquis/Flexible Start Time: 15 Days Standard Acq		
Proposal Budget Estimate:	\$4,704,587.00		

Please read the full advertisement

**Description:**

The Improvements under this District Contract consist of milling and resurfacing. Other incidental work includes: minor roadway widening, traffic monitoring site improvements, and signing and pavement marking improvements on SR 63 (US 27) from north of CR 159A (Potter Woodberry Road) to the Georgia State Line in Gadsden County.  
 The summary of pay items for this project is listed in the Plans.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

**Call Order: 004 Proposal: E3U25**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44364215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44364215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	9,870.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	27,659.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	160.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	842.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	250.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	250.000
	0104- 10- 3	SEDIMENT BARRIER	LF	240.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	269.790
	0107- 2-	MOWING	AC	244.920
	0110- 1- 1	CLEARING & GRUBBING (44364215201)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	647.100
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44364215201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	297.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	297.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	318.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	5,964.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	21,428.000
	0327- 70- 13	MILLING EXISTING ASPHALT PAVEMENT, 1 3/4" AVG DEPTH	SY	7,554.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	98,494.000

**Call Order: 004 Proposal: E3U25**

ALT	Item	Description	Unit	Quantity
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	7,459.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	12,684.500
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	4,796.600
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	150.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,544.300
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	4.000
	0546- 71- 2	RAISED RUMBLE STRIP SET- SHORT TERM	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	54,860.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	38.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	40.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,429.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	16.274
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.126
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	376.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	396.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	13.940
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.094
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	60.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	13.838
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	238.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.660
	0770- 78-	STATIC / WEIGH-IN-MOTION SCALE SYSTEM	EA	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44364215201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	8.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	6.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	4.000
	0701- 18-101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	6.010
	0701- 18-201	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	5.610
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,429.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44364215201)	LS	1.000

**Call Order: 004 Proposal: E3U25**

ALT	Item	Description	Unit	Quantity
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	188.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	198.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.547
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	30.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	119.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.830
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	6.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	6.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.667
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	6.970
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.023
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.460
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.063
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.286