

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03210610 Call Order: 001 Proposal: E3T54 District:03

Counties: JEFFERSON

Road Name: SR 55 (US 221) - RESURFACING

Limits: 54040000

Project(s): 44154415201(*) Federal Aid No: N/A

Total Roadway Length:	6.002 Miles	Contract Days:	210
Total Bridge Length:	0.014 Miles	Letting Date:	06/10/21
Total Proposal Length:	6.016 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Day

Proposal Budget Estimate: \$3,901,790.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of Mill/Resurface, Diversions, Box Culvert, Pipe Cross Drains, Turnout Construction, S&PMs on S.R. 55 (US 221) from the Madison County Line to the Georgia State Line in Jefferson County from MP 0.004 to MP 6.002.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 001 Proposal: E3T54

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0125- 1-	EXCAVATION FOR STRUCTURES	CY	925.000
	0125- 3-	SELECT BEDDING MATERIAL	CY	177.000
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	106.200
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	14,997.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	3,798.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	38.800
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	279.000
	0530- 74-	BEDDING STONE	TN	105.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44154415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44154415201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44154415201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44154415201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	466.200
	0102- 60-	WORK ZONE SIGN	ED	10,328.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	2,170.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	2,384.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	15,724.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	246.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	3,607.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	16.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,388.000

Call Order: 001 Proposal: E3T54

ALT	Item	Description	Unit	Quantity
	0102-115-	TYPE III BARRICADE	ED	1,920.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	210.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	1,924.000
	0104- 10- 3	SEDIMENT BARRIER	LF	9,540.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	120.000
	0107- 1-	LITTER REMOVAL	AC	323.070
	0107- 2-	MOWING	AC	279.900
	0110- 1- 1	CLEARING & GRUBBING (44154415201)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,580.500
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44154415201)	LS	1.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	779.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	585.000
	0285-713-	OPTIONAL BASE, BASE GROUP 13	SY	253.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	1,417.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	84,510.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	7,066.000
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	8,386.700
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	8.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	234.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	77.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	158.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-560-200	STRAIGHT CONCRETE ENDWALLS, 60", DOUBLE, 0 DEGREES, ROUND	EA	2.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	24.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	37.900
	0550- 10-120	FENCING, TYPE A, 5.1-6.0, STANDARD	LF	60.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	19,244.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	13.455
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	140.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	6.663
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	4.952
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44154415201)	LS	1.000
Section 0003 Signing				
	0546- 72- 2	GROUND-IN RUMBLE STRIPS, 8" CYLINDRICAL	GM	12.498
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	8.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	14.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	28.000

Call Order: 001 Proposal: E3T54

ALT	Item	Description	Unit	Quantity
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44154415201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	140.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	11.749
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.957
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	4.952