

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03210513	Call Order: 001	Proposal: E3S70	District:03
Counties:	WAKULLA			
Road Name:	SR 30 (US 98) BIKE PATH/TRAIL			
Limits:	Midpoint			
Project(s):	43992635201(*)	Federal Aid No: N/A		
Project(s):	43992635202	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	395	
Total Bridge Length:	0.000 Miles	Letting Date:	05/13/21	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Day Standard	

Proposal Budget Estimate: \$7,089,712.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of FPID 439926-3-52-01, construction of a 10-foot-wide shared use path, a 1,609 linear foot boardwalk, and signing and pavement markings along SR 30 (US 98) Coastal Hwy From S. of Tower Rd. to SR 61 (US 319) and FPID 439926-3-52-02, construction of a 5-foot-wide sidewalk and signing and pavement markings along SR 30 (US 98) Coastal Hwy thru Panacea in Wakulla County, Florida.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT.

Call Order: 001 Proposal: E3S70

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43992635201)	LS	1.000
	0101- 1-	MOBILIZATION (43992635202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43992635201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43992635202)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	25,675.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	30,020.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,580.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	395.000
	0104- 10- 3	SEDIMENT BARRIER	LF	11,268.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,744.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	711.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	18.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	61.000
	0107- 1-	LITTER REMOVAL	AC	903.020
	0107- 2-	MOWING	AC	545.670
	0110- 1- 1	CLEARING & GRUBBING (43992635201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43992635202)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	28.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	19.000
	0120- 1-	REGULAR EXCAVATION	CY	6,667.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	20,024.800

Call Order: 001 Proposal: E3S70

ALT	Item	Description	Unit	Quantity
	0120- 4-	SUBSOIL EXCAVATION	CY	2,637.200
	0125- 1-	EXCAVATION FOR STRUCTURES	CY	61.000
	0160- 4-	TYPE B STABILIZATION	SY	7,279.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	5,547.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	17,026.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	7,997.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	4,996.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	2,887.300
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	1,326.300
	0400- 2- 8	CONCRETE CLASS II, BULKHEAD	CY	30.700
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	3,254.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	22.000
	0425- 1-529	INLETS, DT BOT, TYPE C, MODIFY	EA	6.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	3.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	5.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	2.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	402.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	210.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	181.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	961.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	1,705.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	187.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	6.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	3.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	5.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	12.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	8.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	6.000
	0455- 2- 7	TIMBER PILING FOR PEDESTRIAN BOARDWALK, PROJECT 439926-3-52-01	LF	7,361.000
	0455- 2- 9	TIMBER TEST PILE FOR PEDESTRIAN BOARDWALK, PROJECT 439926-3-52-01	LF	320.000
	0455- 35-104	STEEL PILING, 10" DIA. PIPE, PROJECT 439926-3-52-01,	LF	2,889.000
	0455-144-101	TEST PILES - STEEL, 10" DIA PIPE, PROJECT 439926-3-52-01	LF	130.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	40.500
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	52.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	2,247.000
	0515- 2-701	PEDESTRIAN BRIDGE RAILING- COATED FENCE MESH, 3.5' PROJECT 439926-3-52-01	LF	3,218.000
	0519- 78-	BOLLARDS	EA	2.000

Call Order: 001 Proposal: E3S70

ALT	Item	Description	Unit	Quantity
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,551.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	318.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,294.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	103.700
	0530- 74-	BEDDING STONE	TN	3.200
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	32,505.000
	0751- 49-100	PEDESTRIAN BOARDWALK- FIBER REINFORCED POLYMER COMPOSITE DECKING, PROJECT 439926-3-52-01	MB	38.300
	0919-456- 4	GRAVEL FILL FOR WALL FOUNDATION, PROJECT 439926-3-52-01 and 439926-3-52-02	CY	1,242.500
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43992635201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43992635202)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	26.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	46.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	4.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	2.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	14.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	18.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	36.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	23.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	581.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	41.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	67.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	236.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	7.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.238
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.017
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.047
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	285.000