

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	03211110	Call Order: 004	Proposal: E3U85	District:03
Counties:	ESCAMBIA			
Road Name:	SR 292 BARRANCAS AVE - RESURFACING			
Limits:	48050000			
Project(s):	44364815201(*)	Federal Aid No: N/A		
Project(s):	44364815202	Federal Aid No: N/A		
Total Roadway Length:	6.944 Miles	Contract Days:	135	
Total Bridge Length:	0.000 Miles	Letting Date:	11/10/21	
Total Proposal Length:	6.944 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Day Standard	

Proposal Budget Estimate: \$2,418,583.00

Please read the full advertisement

**Description:**

The Improvements under this District Contract consist of milling and resurfacing SR 292 Barrancas Avenue from Manchester Street to Bayou Chico Bridge. Project includes sidewalk (ADA), minor drainage, Signing and Pavement Markings and Signalization Improvements and work associated with 443648-1-52-02 including 6 manhole utility adjustments in Escambia County.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

**Call Order: 004 Proposal: E3U85**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44364815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44364815201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	72.000
	0102- 60-	WORK ZONE SIGN	ED	6,450.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	14,175.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	5,610.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	135.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	644.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	135.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	135.000
	0102-115-	TYPE III BARRICADE	ED	160.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	83.000
	0107- 1-	LITTER REMOVAL	AC	29.380
	0107- 2-	MOWING	AC	3.360
	0110- 1- 1	CLEARING & GRUBBING (44364815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	672.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	0.500
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44364815201)	LS	1.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	4,277.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	71,948.000

**Call Order: 004 Proposal: E3U85**

ALT	Item	Description	Unit	Quantity
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	8,379.700
	0425- 1-345	INLETS, CURB, TYPE P-4, PARTIAL	EA	1.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	1.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	5.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	6.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	8.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	11.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	837.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	107.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	416.000
	0527- 2-	DETECTABLE WARNINGS	SF	691.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	252.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44364815201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	5.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,647.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44364815201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,772.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	57.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	514.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.651
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	81.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	256.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	460.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	36.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	36.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.447
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.098
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",1C-30 SKIP OR 3-9 LANE DROP	GM	3.718
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.480
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.849
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.884
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.884
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.884

**Call Order: 004 Proposal: E3U85**

ALT	Item	Description	Unit	Quantity
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.884
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	13.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	360.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	11.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	4.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	4.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	8.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	4.000
	0660- 1-600	LOOP DETECTOR INDUCTIVE, REMOVE- CABINET TO REMAIN	EA	7.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	8.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	4.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000