Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting: 03211110 Call Order: 008 Proposal: E3V20 District:03

Counties: HOLMES, WALTON, WASHINGTON

Road Name: PONCE DE LEON MAINTENANCE - SR 8 SHOULDER REWORK

Limits: 52002000

Project(s): 42214327251(*) Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: THRU 12/31/22

Total Bridge Length: 0.000 Miles Letting Date: 11/10/21

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 15 Days

Proposal Budget Estimate: \$600,000.00

Please read the full advertisement

Description:

The work specified in this Work Document-Driven Contract consists of reshaping ditches and reworking shoulders along State Road 8 (Interstate 10) on a call out basis in Holmes, Walton, and a portion of Washington Counties. These ditches are non-typical and should be re-graded to +/- 3 inches of the original flow line to create a free and unobstructed flow of drainage water. For the purposes of this contract, the original flow line is considered to be the linear projection along the ditch bottom between the invert elevations of immediately adjacent drainage structures. Spoil material removed from ditches and shoulders shall be relocated to FDOT storage pit in Argyle. Mobilization and Maintenance of Traffic are incidental to the pay items listed.

This contract has a budgetary ceiling of \$600,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Call Order: 008 Proposal: E3V20

ALT	Item	Description	Unit	Quantity
Section 0001 SODDING (SY)				
	0104- 10- 3	SEDIMENT BARRIER	LF	1,000.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	60.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	5,000.000
	E570- 5-	FERTILIZER	TN	4.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	280.000
	E573- 1-	HYDRO-SEEDING - APPLICATION OF SLURRY INCLUDING WOOD FIBER, SEED, FERTILIZER, TACKIFIER & DYE	SY	10,000.000
	E575- 1-	SODDING	SY	136,000.000
	E577- 70-	SHOULDER REWORK	SY	140,000.000