

Call Order: 001 Proposal: E3U40

ALT	Item	Description	Unit	Quantity
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	200.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	188.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,712.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	55.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	3.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	293.000
	0102-115-	TYPE III BARRICADE	ED	275.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	110.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	110.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.120
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.070
	0104- 10- 3	SEDIMENT BARRIER	LF	3,375.000
	0110- 1- 1	CLEARING & GRUBBING (22253935201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	242.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	35.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	564.000
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	271.000
	0285-754-	OPTIONAL BASE- GRADED AGGREGATE, 17" FOR PROJECT 222539-3 -52-01	SY	293.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	2,485.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	3,967.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	146.400
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	474.600
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	192.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	13.400
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	269.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	2.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	330.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.604
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	984.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,120.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.115
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.322
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.828
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (22253935201)	LS	1.000
Section 0003 Signing				
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (22253935201)	LS	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.303
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.303

Call Order: 001 Proposal: E3U40

ALT	Item	Description	Unit	Quantity
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.303
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.038
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.038
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.038
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.038