

**Florida Department of Transportation  
 Bid Solicitation Notice and Approximate Quantities**

Letting: 03211014 Call Order: 002 Proposal: E3U77 District:03  
 Counties: CALHOUN  
 Road Name: SR 69 FROM N OF SR 71 TO S OF STAFFORD CREEK - RESURFACING  
 Limits: 47030000  
 Project(s): 44364715201(\*) Federal Aid No: N/A  
 Total Roadway Length: 3.175 Miles Contract Days: 175  
 Total Bridge Length: 0.000 Miles Letting Date: 10/14/21  
 Total Proposal Length: 3.175 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Day Acquis.  
 Proposal Budget Estimate: \$2,394,632.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of milling and resurfacing, intersection reconfiguration, turn lane addition, base work, shoulder treatment, curb and gutters, drainage improvements, sidewalk, highway signing, lighting, and other incidental construction along SR 69 from north of SR 71 to south of Stafford Creek in Calhoun County.

Prequalification is required to bid on this project.

**Call Order: 002 Proposal: E3U77**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44364715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44364715201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44364715201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44364715201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44364715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	10,880.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	420.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	150.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,470.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	41,040.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,393.000
	0102-115-	TYPE III BARRICADE	ED	360.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	23.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,630.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	90.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	55.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	23.000
	0107- 1-	LITTER REMOVAL	AC	163.380
	0107- 2-	MOWING	AC	144.080
	0110- 1- 1	CLEARING & GRUBBING (44364715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	672.000

**Call Order: 002 Proposal: E3U77**

ALT	Item	Description	Unit	Quantity
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	1.000
	0120- 1-	REGULAR EXCAVATION	CY	276.500
	0120- 6-	EMBANKMENT	CY	1,311.200
	0160- 4-	TYPE B STABILIZATION	SY	2,710.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	732.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	2,292.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	40.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	48,440.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	449.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	70.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	4,410.800
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	4,763.800
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	2.000
	0425- 1-529	INLETS, DT BOT, TYPE C, MODIFY	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	3.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	2.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	383.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	78.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	160.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	312.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	1.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	1.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	28.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	219.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	612.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	37.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	27.000
	0527- 2-	DETECTABLE WARNINGS	SF	263.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	52.800
	0530- 74-	BEDDING STONE	TN	38.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	9,588.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	6,883.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,050.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	7.092
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,134.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	453.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.046

**Call Order: 002 Proposal: E3U77**

ALT	Item	Description	Unit	Quantity
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	11.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.049
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	2.094
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44364715201)	LS	1.000
<b>Section 0002 Signing</b>				
	0654- 2- 21	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR, COMPLETE SIGN ASSY- SINGLE DIRECTION	AS	4.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	29.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	23.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	9.000
	0700- 12- 21	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON	AS	1.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	2.336
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	783.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44364715201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,608.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	347.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.046
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	8.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	161.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	1.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.057
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.303
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.936
<b>Section 0003 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	397.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	779.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	618.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	3,930.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	423.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	5.000
	0715- 5- 21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	2.000

**Call Order: 002 Proposal: E3U77**

ALT	Item	Description	Unit	Quantity
	0715- 5- 51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	5.000