

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 03211014      Call Order: 003      Proposal: E3V07      District:03

Counties: SANTA ROSA

Road Name: MILTON MAINTENANCE - SHLDR AND DITCH MAINTENANCE

Limits: Midpoint

Project(s): 42214237215(\*)      Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	60
Total Bridge Length:	0.000 Miles	Letting Date:	10/14/21
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 days

Proposal Budget Estimate: \$250,000.00

Please read the full advertisement

**Description:**

Improvements under this Site-Specific Contract consist of adding concrete ditch pavement, adding paved shoulder, adding concrete shoulder, removing riprap, removing and replacing damaged concrete ditch, removing and replacing buried pipe, installing new buried pipe, removing bag riprap headwalls, installing new headwall, and restoring all disturbed areas, and associated incidental work to prevent erosion and to restore and preserve maximum drainage functionality along a portion of SR 10 (US Hwy 90) at Mile Post 8.0165 in the Pea Ridge area and SR 10 at Mile Post 11.722 in the Milton area of Santa Rosa County, as shown in the Appendices. All work will be confined to the southern right of way of SR 10 between Sheffield Drive and Trice Road, and between Susan Street and Mary Street.

**Call Order: 003 Proposal: E3V07**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ASPHALT REPAIR (MANUAL) (TN)</b>				
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	187.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	634.600
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	1.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	28.100
	0400- 32-	CONCRETE FOR JOINT REPAIR	CY	1.300
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	360.000
	0430-524-200	STRAIGHT CONCRETE ENDWALLS, 24", DOUBLE, 0 DEGREES, ROUND	EA	1.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	751.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	50.000
	E110- 70-	REMOVAL OF FLEXIBLE PAVEMENT	SY	104.000
	E575- 1-	SODDING	SY	959.000