

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03210909 Call Order: 001 Proposal: E3U51 District:03
Counties: WASHINGTON
Road Name: RESURFACING
Limits: 61002000
Project(s): 44364015201(*) Federal Aid No: N/A
Project(s): 44364015202 Federal Aid No: N/A
Total Roadway Length: 7.442 Miles Contract Days: 150
Total Bridge Length: 0.000 Miles Letting Date: 09/09/21
Total Proposal Length: 7.442 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 15 Day Acquis.

Proposal Budget Estimate: \$2,531,467.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of milling and resurfacing SR 273 Campbellton Highway from SR 77 Main Street to the Jackson County Line. All work is to be completed in Washington County. Major items of work include new sidewalk construction from SR 77 to Martin Luther King Drive and drainage improvements along the corridor. FPID 443640-1-52-02 involves utility manhole and valve box adjustments.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 001 Proposal: E3U51

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44364015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44364015201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	12.800
	0102- 60-	WORK ZONE SIGN	ED	9,040.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	7,550.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	728.000
	0102-115-	TYPE III BARRICADE	ED	40.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,325.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	414.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	7.000
	0107- 1-	LITTER REMOVAL	AC	152.170
	0107- 2-	MOWING	AC	152.170
	0110- 1- 1	CLEARING & GRUBBING (44364015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	132.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	2.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44364015201)	LS	1.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	68.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	1,130.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	68,099.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	5,623.400

Call Order: 001 Proposal: E3U51

ALT	Item	Description	Unit	Quantity
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-9.5, PG 76-22	TN	4,763.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	111.50C
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	1.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	4.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	2.000
	0425- 3- 61	JUNCTION BOXES, J-7, <10'	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	2.000
	0425- 6-	VALVE BOXES, ADJUST	EA	5.000
	0430-173-115	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 15", GUTTER DRAIN	LF	4.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	9.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	64.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	8.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	12.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	1,044.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	91.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	463.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	355.000
	0527- 2-	DETECTABLE WARNINGS	SF	56.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	927.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-002, APPROACH TL-3	EA	2.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-002, TRAILING	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	511.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	3.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	81.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	11,316.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	854.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	7.284
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	86.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	207.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.063
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	2.148
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44364015201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	21.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	3.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	16.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	2.000

Call Order: 001 Proposal: E3U51

ALT	Item	Description	Unit	Quantity
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	7.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	5.600
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	1.287
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	854.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44364015201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	86.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	207.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.684
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.777
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	2.148
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	510.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.097
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.097