

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	03220818	Call Order: 003	Proposal: E3V86	District:03
Counties:	LEON			
Road Name:	RESURFACING			
Limits:	55170000			
Project(s):	43775815201(*)	Federal Aid No: N/A		
Total Roadway Length:	1.627 Miles	Contract Days:	60	
Total Bridge Length:	0.000 Miles	Letting Date:	08/18/22	
Total Proposal Length:	1.627 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days Standard Acq	
Proposal Budget Estimate:		\$1,517,909.00		

Please read the full advertisement

Description:

The Improvements under this District Contract consist of Milling and Resurfacing and RRR improvements on SR 369 (US 319) from Wakulla CO Line to S of CR 2204 Oak Ridge Rd, in Leon County.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 003 Proposal: E3V86**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43775815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43775815201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	2.500
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,000.000
	0102- 60-	WORK ZONE SIGN	ED	1,260.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,568.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	134.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,266.000
	0107- 1-	LITTER REMOVAL	AC	14.140
	0107- 2-	MOWING	AC	14.140
	0110- 1- 1	CLEARING & GRUBBING (43775815201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	10.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	271.700
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	23,289.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	1,921.300
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	2,124.100
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,192.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	322.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.199
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.228
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.158
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43775815201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	15.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	7.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	3.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	316.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43775815201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.144
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.313
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.061