

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	03221208	Call Order: 001	Proposal: E3V87	District:03
Counties:	OKALOOSA			
Road Name:	RESURFACING			
Limits:	57090000			
Project(s):	44573415201(*)	Federal Aid No:	N/A	
Project(s):	44573415202	Federal Aid No:	N/A	
Total Roadway Length:	8.052 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	12/08/22	
Total Proposal Length:	8.052 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days Other	
Proposal Budget Estimate:	\$4,883,807.00			

Please read the full advertisement

Description:

The Improvements under this District Contract consist of FPID 445734-1-52-01, SR 285 from SR 20 (John Sims Parkway) to south of SR 293 (MidBay Connector) in Okaloosa County. Existing travel lanes, auxiliary lanes, and paved shoulders will be resurfaced. Additionally, a new sidewalk will be constructed along the west side of SR 285 from Adams Street to CR 190 (College Boulevard). The existing mast arms at the CR 190 (College Boulevard) intersection will be replaced on the existing foundations. Other improvements include signing & pavement markings, signalization improvements, and ADA improvements. FPID 445734-1-52-02 consists of adjusting utility manholes and valve boxes.

PREQUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 001 Proposal: E3V87

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44573415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44573415201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	6.300
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44573415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	208.000
	0102- 60-	WORK ZONE SIGN	ED	9,498.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	28,744.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	46,269.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	155.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,136.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	360.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	360.000
	0104- 10- 3	SEDIMENT BARRIER	LF	204.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	72.000
	0107- 1-	LITTER REMOVAL	AC	114.580
	0107- 2-	MOWING	AC	101.710
	0110- 1- 1	CLEARING & GRUBBING (44573415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,295.000

Call Order: 001 Proposal: E3V87

ALT	Item	Description	Unit	Quantity
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	296.100
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44573415201)	LS	1.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	54,763.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	20,018.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	3,765.000
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	5,141.400
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	3.000
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,055.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	193.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,670.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,001.000
	0527- 2-	DETECTABLE WARNINGS	SF	846.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,808.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	1,009.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,430.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.378
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.043
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	4,448.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	973.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	9.756
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.073
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	94.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	12.750
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	877.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	6.777
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.258
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44573415201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	4.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	13.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,810.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44573415201)	LS	1.000

Call Order: 001 Proposal: E3V87

ALT	Item	Description	Unit	Quantity
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,448.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	973.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.073
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	94.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	877.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.258
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,149.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	3.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	3.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.189
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.043
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.252
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.250
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	2.259
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	1,618.000
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	103.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	7.000
	0649- 22- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL ON EXISTING FOUNDATION, SINGLE ARM 70'	EA	4.000
	0649- 26- 1	STEEL MAST ARM ASSEMBLY, REMOVE, POLE ONLY- ENTIRE FOUNDATION REMAINS	EA	4.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	4.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	4.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	8.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	8.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	1.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	11.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	12.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	7.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	1.000

Call Order: 001 Proposal: E3V87

ALT	Item	Description	Unit	Quantity
	0670- 5-500	TRAFFIC CONTROLLER ASSEMBLY, RELOCATE CONTROLLER WITH CABINET	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	9.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	10.000