

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03221208	Call Order: 002	Proposal: E3W27	District:03
Counties:	GADSDEN			
Road Name:	RESURFACING			
Limits:	50030000			
Project(s):	43464515201(*)	Federal Aid No:	N/A	
Project(s):	43464515202	Federal Aid No:	N/A	
Total Roadway Length:	3.920 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	12/08/22	
Total Proposal Length:	3.920 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days Standard Acq	

Proposal Budget Estimate: \$4,849,543.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of milling and resurfacing SR 10 (US 90) from W of Flying J to Leon County Line in Gadsden County. This includes existing travel lanes, auxiliary lanes, median openings, and paved shoulders. There will also be some minor widening, guardrail upgrades, drainage work, and signalization. This work will be done under FPID 434645-1-52-01. The joints for Bridge #500920 will be replaced under FPID 434645-1-52-02.

PREQUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Call Order: 002 Proposal: E3W27

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43464515201)	LS	1.000
	0101- 1-	MOBILIZATION (43464515202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43464515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43464515202)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	77.100
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,560.000
	0102- 60-	WORK ZONE SIGN	ED	6,600.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	57,150.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	300.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	328.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	300.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	300.000
	0102-115-	TYPE III BARRICADE	ED	1,500.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	600.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	600.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	88.000
	0104- 10- 3	SEDIMENT BARRIER	LF	21,875.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	31.000
	0107- 1-	LITTER REMOVAL	AC	184.100
	0107- 2-	MOWING	AC	154.440

Call Order: 002 Proposal: E3W27

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (43464515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	43.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	239.800
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43464515201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	932.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	758.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	373.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	2,329.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	29,119.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	19,880.000
	0327- 70- 13	MILLING EXISTING ASPHALT PAVEMENT, 1 3/4" AVG DEPTH	SY	421.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	27,971.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	2,419.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	293.700
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	21.400
	0334- 1- 57	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, HIGH POLYMER	TN	6,085.900
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	1,257.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,366.900
	0337- 7- 93	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, HIGH POLYMER	TN	2,976.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	159.700
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	1.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	21.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	1.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	634.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	71.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	487.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,775.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	2.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	2.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, TRAILING	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,534.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	3.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	3.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,158.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	15,337.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,678.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.616

Call Order: 002 Proposal: E3W27

ALT	Item	Description	Unit	Quantity
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,104.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.308
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.160
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43464515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43464515202)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	2.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	4.000
	0701- 18-101	PROFIED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	1.739
	0701- 18-201	PROFIED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	1.329
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	6.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	16.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,399.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	150.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43464515201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	601.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	421.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.043
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	61.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	15.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	271.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.459
	0711- 14-141	THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.117
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	26.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	26.000
	0711- 14-341	THERMOPLASTIC, PREFORMED, BLACK, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.117
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.845
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.716
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.138
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.787
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.133
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.115

Call Order: 002 Proposal: E3W27

ALT	Item	Description	Unit	Quantity
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.103
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.103
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.103
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.103
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,375.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	655.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	145.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	18.000
	0646- 1- 30	ALUMINUM SIGNALS POLE, INSTALL	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	1.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	10.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	16.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	7.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000