

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

| | | | | |
|---------------------------|--|----------------------------|--------------------|-------------|
| Letting: | 03221208 | Call Order: 003 | Proposal: E3W59-R0 | District:03 |
| Counties: | JACKSON, WASHINGTON | | | |
| Road Name: | MARIANNA MAINTENANCE - DRAINAGE REPAIR AND REPLACEMENT | | | |
| Limits: | Midpoint | | | |
| Project(s): | 42212227227(*) | Federal Aid No: N/A | | |
| Total Roadway Length: | 0.000 Miles | Contract Days: | Thru 12/31/2023 | |
| Total Bridge Length: | 0.000 Miles | Letting Date: | 12/08/22 | |
| Total Proposal Length: | 0.000 Miles | Contract Execution Days: | 10 | |
| | | Special Start Date: | N/A | |
| | | Aquis/Flexible Start Time: | | |
| Proposal Budget Estimate: | \$150,000.00 | | | |

Please read the full advertisement

Description:

The Improvements under this Work Document-Driven Contract consists of repair and/or replacement of drainage elements on various roads in Jackson and Washington Counties, including the known locations shown in the Appendices. This work includes dewatering, desilting, cleaning, and repairing leaks in pipes and manholes, installing pipe liner, repairing, or replacing inlets and mitered end sections. This contract has a budgetary ceiling of \$150,000.00. Maintenance of Traffic and Mobilization are incidental to the pay items listed.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

A Proposal Guaranty will not be required on indefinite quantity contracts, such as work document driven contracts, with an advertised budget amount of \$150,000 or less regardless of the bid amount.

Call Order: 003 Proposal: E3W59-R0

| ALT | Item | Description | Unit | Quantity |
|--|--------------|---|------|----------|
| Section 0001 CLEAN DRAINAGE STRUCTURES (LF) | | | | |
| | 0104- 10- 3 | SEDIMENT BARRIER | LF | 125.000 |
| | 0425- 3- 50 | JUNCTION BOX, DRAINAGE, REPAIR | EA | 2.000 |
| | 0425- 15- 41 | INLET TOP, REPAIR, CURB INLET | EA | 2.000 |
| | 0425- 15- 42 | INLET TOP, REPAIR, DITCH BOTTOM INLET | EA | 2.000 |
| | 0425- 15- 51 | INLET TOP, REPLACE, CURB INLET | EA | 2.000 |
| | 0425- 15- 52 | INLET TOP, REPLACE, DITCH BOTTOM INLET | EA | 2.000 |
| | 0430- 96- | DRAINAGE PIPE REPAIR- CONCRETE COLLAR AT JOINT | EA | 4.000 |
| | 0430-174-118 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD | LF | 16.000 |
| | 0430-174-124 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD | LF | 16.000 |
| | 0430-174-130 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD | LF | 16.000 |
| | 0430-174-136 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD | LF | 8.000 |
| | 0430-174-142 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 42"SD | LF | 8.000 |
| | 0430-174-148 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 48"SD | LF | 8.000 |
| | 0430-174-154 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 54"SD | LF | 8.000 |
| | 0430-174-160 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 60"SD | LF | 8.000 |
| | 0430-524-100 | STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND | EA | 1.000 |
| | 0430-530-100 | STRAIGHT CONCRETE ENDWALLS, 30", SINGLE, 0 DEGREES, ROUND | EA | 1.000 |
| | 0430-536-100 | STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND | EA | 1.000 |
| | 0430-542-100 | STRAIGHT CONCRETE ENDWALLS, 42", SINGLE, 0 DEGREES, ROUND | EA | 1.000 |
| | 0430-548-100 | STRAIGHT CONCRETE ENDWALLS, 48", SINGLE, 0 DEGREES, ROUND | EA | 1.000 |
| | 0430-984-125 | MITERED END SECTION, OPTIONAL ROUND, 18" SD | EA | 2.000 |
| | 0430-984-129 | MITERED END SECTION, OPTIONAL ROUND, 24" SD | EA | 2.000 |
| | 0430-984-133 | MITERED END SECTION , OPTIONAL ROUND, 30" SD | EA | 2.000 |
| | 0430-984-138 | MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN | EA | 2.000 |
| | 0430-984-140 | MITERED END SECTION , OPTIONAL ROUND, 42" SD | EA | 2.000 |
| | 0430-984-141 | MITERED END SECTION , OPTIONAL ROUND, 48" SD | EA | 2.000 |
| | 0430-984-142 | MITERED END SECTION , OPTIONAL ROUND, 54" SD | EA | 1.000 |
| | 0430-984-143 | MITERED END SECTION , OPTIONAL ROUND, 60" SD | EA | 1.000 |
| | E425- 73- 1 | CLEANING MANHOLES AND INLETS (MECHANICAL) | EA | 2.000 |
| | E425- 73- 2 | REPAIR LEAKS IN MANHOLES AND INLETS | EA | 2.000 |
| | E425- 73- 5 | CLEANING MANHOLES AND INLETS (MANUAL) | EA | 4.000 |
| | E430- 94- 1 | DESILT PIPE, 0 to 24" | LF | 25.000 |
| | E430- 94- 2 | DESILT PIPE, 25-36" | LF | 25.000 |
| | E430- 94- 3 | DESILT PIPE, 37-48" | LF | 25.000 |
| | E430- 94- 4 | DESILT PIPE, 49-60" | LF | 25.000 |
| | E431- 1- 21 | PIPE LINER, CURED IN PLACE, 0-24" | LF | 25.000 |
| | E431- 1- 22 | PIPE LINER, CURED IN PLACE, 25-36" | LF | 25.000 |
| | E431- 1- 23 | PIPE LINER, CURED IN PLACE, 37-48" | LF | 130.000 |
| | E431- 1- 24 | PIPE LINER, CURED IN PLACE, 49-60" | LF | 70.000 |
| | E431- 1- 25 | PIPE LINER, CURED IN PLACE, 61" AND GREATER | LF | 20.000 |